

मोलावा आज़ाद वेशवल उर्दू यूनिवरिरिटी مولاتا آزاد تيشتل أر دويو تيورتى

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998 (Accredited "A+" Grade by NAAC)

Notice Inviting Quotation

NIQ No. Oh /MANUU/CD/2023-24 dated 23-06-2023

S.No	Name of the Work	Construction of platform for Rice Boiler in Gulzar Girls Hostel in MANUU Campus, Gachibowli, Hyderabad.				
1.	Time Allowed for work completion	10 days				
2	Date of start of Bid Submission	22-06-2023 at 11:00 AM				
3.	Last date & Time for submission of Bids	30-06-2023 at 11:00 AM				

Executive Engineer

कार्यकारी अभियंता/ Executive Engineer इंजीनियरिंग अनुभाग/ Engineering Section मौलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी Maulana Azad National Urdu University गञ्जीबौली, हैदराबाद - ५०००३२ Gachibowli, Hyderabad-500 032.

मोलावा आज़ाद वेशवल उर्दू यूविवर्सिटी के जिल्ला है । जिल्ला आज़ाद वेशवल उर्दू यूविवर्सिटी

MAULANA AZAD NATIONAL URDU UNIVERSITY



A Central University established by an Act of Parliament in 1998 (Accredited "A+" Grade by NAAC)

Name of the Work: Construction of platform for Rice Boiler in Gulzar Girls Hostel in MANUU Campus, Gachibowli, Hyderabad.

1) The estimate amount is inclusive of GST.

Comparative statement for Quoted rates shall be based on rates inclusive of GST.

3) The Bidder should intimate GST percentage separately.

SCHEDUL		Unit	Qty	Rate		Amount
DSR No.	Description of item			In fig	In words	
6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in:					
6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	0.85			
2.25(a)	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	cum	2			
4.2.2A	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) including manufactured sand derived from Recycled Concrete Aggregate (RCA) upto 25% : 3 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA) upto 25%)).	cum	1			
11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (1 cement: 4 coarse sand):					
11.26.1	25 mm thick	sqm	13.5	5		
5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.					
5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	75			

मोलावा आज़ाद वेशवल उर्दू यूविवर्सिटी किता है। जिल्ला आज़ाद वेशवल उर्दू यूविवर्सिटी

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998 (Accredited "A+" Grade by NAAC)

DSRNo.	Description of item	Unit	Qty	Rate		Amount
				In fig	In words	
15.25	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	sqm	10			
	Total Amount (excludingGST) Add GST Total Amount					

Term and conditions:

- The work should be carried out strictly as per the specifications and as per the directions of the Engineer-in-charge.
- Time allowed for completion of work is 10 days from the date of issue of Work Order.
- 3) The rate shall include the cost of all labour, materials and all the operations involved as described in the specification of item and nothing extra shall be paid on whatsoever account.
- 4) The rate should be quoted both in figures and works which should include all taxes etc.
- 5) The rate should be applicable to all heights and leads and transportation of materials and tools etc.
- 6) Defect liability period 6 months from the date of completion of the work
- The payment shall be made as per actual execution and measurement at site after the completion of the work in all aspects and to the satisfactory level.
- The Income tax shall be deducted as per applicable and notified by Govt.of India.
- In case of delay in completion of the contract, LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.

Copy to:

- 1) The Office of the Registrar,
- Director CIT for uploading in the University website.

Notice Board.

कार्यकारी अभियंता/ Executive Engineer

इंजीनियरिंग अनुभाग/ Engineering Section मौल ना आज़ाद नेशनल उर्दू यूनिवर्सिटी Maulana Azad National Urdu University गचीबौली, हैदराबाद - ५०००३२ Gachibowii, Hyderabad-500 032.