



مولانا آزاد نیشنل اردو یونیورسٹی

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998
(Accredited "A+" Grade by NAAC)

Notice Inviting Quotation


NIQ No **12**/MANUU/BOT/Horticulture/F33/2/2023-24 dated : 11-08-2023

S.No	Name of the Work	Construction of Green House Shed for Botany Section of School of Sciences in MANUU Campus Gachibowli, Hyderabad.
1.	Time Allowed for work completion	15 days
2.	Date of start of Bid Submission	11-08-2023 at 12:00 Noon
3.	Last date & Time for submission of Bids	18-08-2023 at 11:00 AM

Details of Contractor/Firm

1.	Name of the Firm	
2.	Address	
3.	Phone No	
4.	Email Id	
5.	Firm Registration	
6.	GST Registration	
7.	PAN Card No	

Signature of Contractor with Stamp


कार्यकारी अभियंता / Executive Engineer
इंजीनियरिंग अनुभाग / Engineering Section
मौलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी
Maulana Azad National Urdu University
गञ्जीबौली, हैदराबाद - ५०००३२
Gachibowli, Hyderabad-500 032.





Name of the Work : Construction of Green House Shed for Botany Section of School of Sciences in MANUU Campus Gachibowli, Hyderabad.

- 1) The estimate amount is inclusive of GST.
- 2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
- 3) The Bidder should intimate GST percentage separately.

SCHEDULE OF QUANTITIES

DSR No.	Description of item	Unit	Qty	Rate		Amount
				In fig	In words	
2.8	Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.					
2.28.1	All kinds of soil	Sqm	230			
2.8	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m					
2.8.1	All kinds of soil	cum	1.85			
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level					
4.1.3A	1:2:4 (1 cement : 2 coarse sand (zone-III) including manufactured sand derived from Recycled Concrete Aggregate (RCA) upto 25% : 4 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA) upto 25%)	cum	1.85			
13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade					
13.61.1	Two or more coats on new work	sqm	30			

कार्यकारी अभियंता/ Executive Engineer
इंजीनियरिंग अनुभाग/ Engineering Section
मौलाना آزاد नेशनल उर्दू यूनिवर्सिटी
Maulana Azad National Urdu University
गञ्जीबौली, हैदराबाद - ५०००३२
Gachibowli, Hyderabad-500 032.

Gachibowli, Hyderabad – 500 032.

☎ 8333853369 ☎ 040 23120600 Extn. 1360,1361 & 1362

website: www.manuu.ac.in

✉ Email: executive@manuu.ac.in

11/8/23



DSRNo.	Description of item	Unit	Qty	Rate		Amount
				In fig	In words	
NSR	Fabrication of old available 50 mm pipe with all necessary fittings etc as per the direction of Engineer-in-charge.	LS				
NSR	Providing and fixing green mesh of required transparency	LS				
NSR	Electrical Work	LS				
Total Amount (excluding GST) _____						
Add GST _____						
Total Amount _____						

Term and conditions:

- 1) The work should be carried out strictly as per the specifications and as per the directions of the Engineer-in-charge.
- 2) Time allowed for completion of work is 15 days from the date of issue of Work Order.
- 3) The rate shall include the cost of all labour, materials and all the operations involved as described in the specification of item and nothing extra shall be paid on whatsoever account.
- 4) The rate should be quoted both in figures and words which should include all taxes etc.
- 5) The rate should be applicable to all heights and leads and transportation of materials and tools etc.
- 6) Defect liability period 6 months from the date of completion of the work
- 7) The payment shall be made as per actual execution and measurement at site after the completion of the work in all aspects and to the satisfactory level.
- 8) The Income tax shall be deducted as per applicable and notified by Govt. of India.
- 9) In case of delay in completion of the contract, LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.

Copy to :

- 1) The Office of the Registrar,
- 2) Director CIT for uploading in the University website.
- 3) Notice Board.

Signature
 کارکنی انجینئر/ Executive Engineer
 انجینئرنگ سیکشن/ Engineering Section
 مولانا آزاد نیشنل اردو یونیورسٹی
 Maulana Azad National Urdu University
 گچی بولی، ہیدرآباد - ۵۰۰۰۳۲
 Gachibowli, Hyderabad-500 032.

Gachibowli, Hyderabad – 500 032.