

Notice Inviting Tender

NIQ No. 12 /MANUU/CD/2022-23/

Sealed item rate quotations are invited for installation of aluminium partition in Department of translation and publication, MANUU Campus. Hyderabad to reach the office of the Executive Engineer, MANUU Gachibowli, Hyderabad up to 11.00 AM on or before 08-11-2022. Blank quotation form shall be downloaded from the University's website. 10

Name of the Work: Installation of aluminium partition in Department of translation and publication, MANUU Campus

Name of the Firm						
Address						
Phone						
Email						
GST Registration						
S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
As per attached Schedule of Quantities						

Term and conditions:

1. The work shall be executed as per direction of Engineer-in-Charge.
2. Time allowed for completion of work is 07 days from the date of issue of Work Order.
3. The payment shall be made as per actual execution and measurement at site.
4. The rates quoted shall be inclusive of all the taxes and nothing extra shall be paid.
5. The Income tax shall be deducted as per applicable and notified by Govt. of India.
6. The agency shall take all safety precautions to avoid all accidents. If any untoward incident/accident occurs during the period of work, the agency shall solely be responsible for the same and consequences thereof.
7. In case of delay in completion of the contract, LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.
8. The University reserves the right to cancel the NIQ without specifying any reason.

Contractor Sign (With Stamp)

Address

- Copy to :
1. The Office of the Registrar
 2. Director CIT for uploading in the University website
 3. Notice Board


 Executive Engineer
 कार्यकारी अभियंता/ Executive Engineer
 इंजीनियरिंग अनुभाग/ Engineering Section
 मौलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी
 Maulana Azad National Urdu University
 गच्छीबौली, हैदराबाद - ५०००३२
 Gachibowli, Hyderabad-500 032.

Gachibowli, Hyderabad – 500 032.

☎ 8463994994 ☎ 040 23120600 Extn. 1360,1361 & 1362. ✉ Email: executive_engineer@manuu.edu.in
 website: www.manuu.ac.in

SCHEDULE OF QUANTITIES
of Work: Aluminium Partition work in Dept. of Translation and Publication, MANUU Campus Hyd.

DSR-2021 Item No	Description	Unit	Qty	Rate		Amount
				In Fig	In Words	
21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P.brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : 21.1.1 For fixed portion					
21.1.1.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	88			
21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)					
21.1.2.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	7			
21.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer in-charge.					


Executive Engineer
 Maulana Azad National Urdu University, Hyd

SCHEDULE OF QUANTITIES
Schedule of Work: Aluminium Partition work in Dept. of Translation and Publication, MANUU Campus Hyd.

DSR-2021 Item No	Description	Unit	Qty	Rate		Amount
				In Fig	In Words	
21.2.1	Pre-laminated particle board with decorative lamination on both sides	Sqm	8.5			
21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item):					
21.3.2	With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm)	Sqm	4.5			
21.13	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	each	1			
9.97	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete	each	1			
9.97.3	200x10 mm Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :					
9.100	125 mm Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	each	2			
9.100.1		each	1			
8	Total Amount					


Executive Engineer
Maulana Azad National Urdu University, Hyd.