

Notice Inviting Tender

NIQ No. 06 /MANUU/CD/2022-23/

Sealed item rate quotations are invited for Repair & Renovation of Room No.1 of Library for Dara Shikoh Corner at MANUU Campus. Hyderabad to reach the office of the Incharge Engineering Section, MANUU Gachibowli, Hyderabad up to 11.00 AM on or before 15/07/2022. Blank quotation form can be downloaded from the website.

Name of the Work: Repair & Renovation of Room No.1 of Library for Dara Shikoh Corner at MANUU Campus.

Name of the Firm						
Address						
Phone						
Email						
GST Registration						
PAN Card No.						
S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
As per attached Schedule of Quantities						

Term and conditions:

1. The work shall be executed as per direction of Engineer-in-Charge.
2. Time allowed for completion of work is 04 days from the date of issue of Work Order.
3. The payment shall be made as per actual execution and measurement at site.
4. The rates quoted shall be inclusive of all the taxes and nothing extra shall be paid.
5. The Income tax shall be deducted as per applicable and notified by Govt. of India.
6. The agency shall take all safety precautions to avoid all accidents. If any untowards incident/accident occurs during the period of work, the agency shall solely be responsible for the same and consequences thereof.
7. In case of delay in completion of the contract, LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.

Contractor Sign (With Stamp)

Address

[Signature]
I/c Engineering & CD Section
I/c Engineering Section
Maulana Azad National Urdu Univer. .
Gachibowli, Hyderabad-32

- Copy to :
1. The Office of the Registrar
 2. Director CIT for uploading in the University website
 3. Notice Board

Gachibowli, Hyderabad – 500 032.

☎ 08463994994 ☎ 040 23120600 Extn. 1360,1361 & 1362. ✉ Email: executive_engineer@manuu.edu.in
website: www.manuu.ac.in



SCHEDULE OF QUANTITIES


Name of the work : Repair & Renovation of Room No.1 of Library for Dara Shikoh Corner at MANUU Campus.

S.No.	Description	Qty	Unit	Rate		Amount
				In Figs	In Words	
1	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.					
1.1	With Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process to give stable crystalline structure with minimum compressive strength 225 kg/ sq. cm, bending strength 100 kg/sq. cm , of size 595x595 mm, having perforation of dia. 10 mm with minimum perforated area 18 % with non woven tissue on the back side, having an NRC (Noise Reduction Coefficient) of 0.85, with 50 mm thick rockwool of 48 kg /cum backing.	17	Sqm			
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture,additional coats wherever required to achieve even shade and colour. including applying					
2.1	Two coats	75	Sqm			
3	Supply, Installation, testing and commissioning of round recessed LED luminaire including LED lamp with lumens not less than 1200 lumens and wattage not more than 15 Watts, colour temperature not less than 5700K, non yellowing diffuser, complete with LED module, driver unit, built in 2 KV surge protector duly wired, directly on false ceiling/wall including connections with 1.5 Sq.mm FRLS, PVC insulated , copper conductor, single core cable and earthing etc., as required.	5	Each			
Total						

Term and conditions:

1. The work shall be executed as per direction of Engineer-in-Charge.
2. Time allowed for completion of work is 04 days from the date of issue of Work Order.
3. The payment shall be made as per actual execution and measurement at site.
4. The rates quoted shall be inclusive of all the taxes and nothing extra shall be paid.
5. The Income tax shall be deducted as per applicable and notified by Govt. of India.
6. The agency shall take all safety precautions to avoid all accidents. If any untowards incident/accident occurs during the period of work, the agency shall solely be responsible for the same and consequences thereof.
7. In case of delay in completion of the contract, LD at 1/2 percent of the contract value per day of delay subject to the maximum of 10% of contract value/work order will be levied without assigning any reason unless extension is obtained in writing from the office on valid ground before completion date.

Contractor Sign (With Stamp)


 I/c Engineering & CD Section
 Maulana Azad National Urdu University