मोलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी مولانا آزاد تيشل أروويو نيورسى

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998 (Accredited "A" Grade by NAAC)



HY/ADMN/ENGG/F.214/2021/05

Dated: 08/04/2021

Notice Inviting Quotation

NIQ No. 6) / MANUU/ES/F.214/2020-21/

dated: 08/04/2021

Sealed item rate quotations are invited for painting work at LQ 3 and one room at Finance Section, Admin building, in MANUU Campus to reach the office of the Incharge Engineering Section, MANUU Gachibowli, Hyderabad up to 3.00 pm on or before 19/04/2021. The quotation will be opened on the same day at 3.30 pm. Blank quotation form can be downloaded from the website.

Name of the work: Painting work at LQ 3 and One Room at Finance Section, Admin building, in the MANUU Campus, Hyderabad

Item No.	Description of item	Quantity	Unit	Rate		Amount
				In fig	In words	
	A	As per attache	d Sche	dule of Q	uantities	•

Term and conditions:

- 1. The work shall be executed as per CPWD specification Vol-I & II as per manufacturer's specifications.
- 2. Time allowed is 10 days.
- 3. The payment shall be as per actual execution and measurement at site.
- 4. The rates quoted are net and nothing extra shall be paid on account of taxes, octoria etc.
- 5. The Income tax and GST shall be deducted as per applicable and notified by Govt. Of India.

CONTRACTOR

Address

I/c Engineering & CD Section

fort

Copy to:

1. The Office of the Registrar

2. The Director CIT for uploading in the University website.

3. Notice Board

Schedule of Quantity

Name of Work: Painting at LQ-3 and one room at finance section, Admin. Building in MANUU Campus

S.No	Description	Qty	TT 1	Rate		Amount
	Description		Unit	in Figure	in words	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	20	Sqm			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	20	Sqm			
	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.					
3.1	Two coat	430	Sqm	3		4) 1
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:	e e				
4.1	One or more coats on old work	40	Sqm		, , ,	
9 5	Total	8				

Term and conditions:

- 1. The work shall be executed as per CPWD specification Vol-I &II as per manufacturer's specifications.
- 2 Time allowed is 10 days.
- 3. The payment shall be as per actual execution and measurement at site.
- 4. The rates quoted are net and nothing extra shall be paid on account of taxes, octoria etc.
- 5. The Income tax and GST shall be deducted as per applicable and notified by Govt.of India.

Contractor Sign Address

I/c Engineering & CD Section

fort