



MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998

(Accredited "A" Grade by NAAC)

No. MANUU/CD/F./2020-21/ 327

Dated: 19/08/2020

29.

Notice Inviting Quotation

NIQ No. 10 MANUU/CD/2020-21/

Sealed item rate quotations are invited for Repair & renovation works in pantry attached to Vice- Chancellor's office at MANUU Campus to reach the office of the Executive Engineer, Engineering Section, MANUU Gachibowli, Hyderabad up to 3.00 pm on or before 24/08/2020. The quotation will be opened on the same day at 3.30 pm in the presence of intending bidders. Blank quotation form can be obtain from the above office during office hours in all working days and upto 2.00 pm on 24/08/2020.

Name of the Work: *Repair & renovation work s in pantry attached to VC's Peshi at MANUU Campus, Hyderabad.*

S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
As per attached Schedule of Quantities						

Term and conditions:

1. The work shall be executed as per CPWD specification Vol-I &II as per manufacturer's specifications.
2. Time allowed is 07 days.
3. The payment shall be as per actual execution and measurement at site.
4. The rates quoted are net and nothing extra shall be paid on account of taxes, octoria etc.
5. The Income tax and GST shall be deducted as per applicable and notified by Govt.of India.

CONTRACTOR

Address

Copy to

1. The Office of the Registrar
2. Director CIT for uploading in the University website
3. Notice Board


Executive Engineer
कार्यकारी अभियंता/ Executive Engineer
इंजीनियरिंग अनुभाग/ Engineering Section
मौलाना आजाद नेशनल उर्दू यूनिवर्सिटी
Maulana Azad National Urdu University
गच्छीबोली, हैदराबाद-500 032
Gachibowli, Hyderabad-500 032.

Gachibowli, Hyderabad – 500 032.

Tel: +91 04023006602 Fax:23006603 Email: registrar@manuu.edu
website: www.manuu.ac.in

Schedule of Quantities

Name Of Work: Repair & renovation works in Pantry attached to VC's Peshi at MANUU, Hyderabad

S.No	Description of Item	Unit	Quantity	Rate		Amount
				In Fig	In Words	
1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.					
1.1	Cement mortar 1:3 (1 cement :3 coarse sand)	Sqm	8			
2	12 mm cement plaster of mix :					
2.1	1:4 (1 cement: 4 fine sand)	Sqm	8			
3	15 mm cement plaster on the rough side of single or half brick wall of mix :					
3.1	1:4 (1 cement: 4 fine sand)	Sqm	7			
4	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete in shelves, including setting in cement mortar 1:3 (1cement : 3 coarse sand), cost of required centering, shuttering and finishing with neat cement punning on exposed surfaces but , excluding the cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	0.2			
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.					
5.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	20			
6	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size,approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.					
6.1	Granite of any colour and shade					

6.1.1	Area of slab upto 0.50 sqm	Sqm	3		
7	Extra for providing opening of required size & shape for wash basin/kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete	each	1		
8	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm,including painting of fittings and brackets, cutting and making good the walls wherever required :				
8.1	Kitchen sink without drain board of size 610x510 mm bowl	each	1		
9	Providing and fixing P.V.C. waste flexible pipe of 40mm dia for sink or wash basin including P.V.C. waste fittings complete.		1		
10	Providing and fixing 15 mm C.P. brass tap	each	1		
11	Providing and fixing 100 mm S.C.I. trap with inlet and outlet	each	1		
12	Providing and fixing G.I. Pipes of 15 mm dia nominal bore complete with G.I. fittings and clamps,i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall:	metre	4		
13	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same etc. complete as per direction of Engineer-in-charge.	each	1		
14	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
14.1	For thickness of tiles 10 mm to 25 mm sqm	Sqm	3		
15	Providing and laying vitrified floor tiles of size 600x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades.laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand),jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.	Sqm	3		

16	Providing and fixing cup board shutters 25 mm thick, with Pre-laminated flat pressed three layer particle board or graded wood particle board IS: 12823 marked, exterior grade (Grade I Type II), having one side decorative lamination and other side balancing lamination, including IInd class teak wood lipping of 25 mm wide x12 mm thick with necessary screws and bright finished stainless steel piano hinges,magnetic catchers, tower bolts, door handles/ knobs and all other types of necessary fittings etc. complete as per the site conditions complete as per direction of the Engineer-in-Charge	Sqm	4		
17	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	15		
18	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
18.1	New work (two or more coats) over and including water	Sqm	15		
	Total				

In words:

Conditions:

1. The work shall be completed as per CPWD specifications Vol I&II with up to date corrections slips.
2. The rates quoted shall be net inclusive of all Taxes, loyalties, octroi etc nothing extra shall be paid.
3. Time allowed 3 Days.
4. The payment shall be as per actual execution and measurements reorded at site.
5. Due recoveries like IT etc shall be deducted from the gross amount of bill

Signature of contractor with Seal


Executive Engineer
MANUU, Hyderabad
कार्यकारी अभियंता/ Executive Engineer
इंजीनियरिंग अनुभाग/ Engineering Section
मौलाना आज़ाद नेशनल उर्दू यूनिवर्सिटी
Maulana Azad National Urdu University
गञ्जीबोली, हैदराबाद-500 032
Gachibowli, Hyderabad-500 032.