

NOTICE INVITING TENDER

For Construction of Silver Jubilee gate-II behind CIT building, MANUU Campus, Gachibowli, Hyderabad

[Tender published on e-procurement (CPPP) of GOI]

MANUU/ENGG/2022-23/001
Open/ Work Contract/ Single Stage Two Envelop System through e-
Procurement
Online on CPPP portal only
Construction of Silver Jubilee gate-II behind CIT building, MANUU
Campus Gachibowli, Hyderabad
Rs. 26,00,094/-
Rs. 52,002/- (2% of the tender value)
Rs. 78,003/- (3% of the tender value)
30 days from last date of submission of bids
14-11-2022 at 3:00PM
22-11-2022 at 3:00PM
23-11-2022 at 3:00PM
Technically qualifying bidders will be informed through CPPP
reclinically quantying bidders will be informed through Crrr
The original EMD should reach the Engineering Section, MANUU up to
3:00 PM on 22.11.2022.

Sd/-Executive Engineer MANUU

Item rate (Unit Rate) Contract

Table of Contents

Name of Work: Construction of Silver Jubilee gate-II behind CIT building, MANUU Campus, Gachibowli, Hyderabad

Sl. No.	Content	Page
1	Notice inviting tender	3
2	Instructions for Bidders/contractors.	4-8
3	Tenders Application, Tender Submission and Tender opening	9
4	C.P.W.D - 7	10-12
5	Proforma of Schedules A to F	13-16
6	Terms & Conditions for Original & Maintenance Works	17-18
7	Annexure-I to Annexure-V: Form of Earnest Money, Performance / Bank Guarantee and Sample letter for Acceptance & Commencement and Affidavit "J".	19-24
8	Integrity Pact	25-31
9	Special conditions regarding contractor's obligations under EPF & ESI	32
10	Special conditions regarding contractor's obligations under MINES & Quarries	33
11	List showing preferred brands/makes/manufacturers	34-38
12	Schedule of Quantities	39-48
13	Check list for Technical eligibility of Tender	49
14	Bank Details of the Contractors	50

Certified that this N.I.T contains 1 to 50 pages (Fifty) only.

Executive Engineer MANUU, Hyderabad.



Notice Inviting Tender

For Construction of Silver Jubilee Gate-II behind CIT building, MANUU Campus, Gachibowli, Hyderabad

Tender No: MANUU/ENGG/2022-23/001

The Executive Engineer, MANUU, Hyderabad on behalf of Registrar, MANUU invites item rate (unit rate) bids from eligible contractors of CPWD/MES/Railways/BSNL /Telangana PWD/Central/ State Autonomous bodies/ Undertakings etc. (Civil Category) through online mode on CPPP for Construction of Silver Jubilee gate-II behind CIT building, MANUU Campus, Gachibowli, Hyderabad. The bids are to be submitted online on CPP portal only before 22.11.2022 at 3:00PM. The required information will be available on 'eprocurement.gov.in' & 'www.manuu.ac.in'. For any query, you may please contact Mr. S Nageswara Reddy, Executive Engineer, Engineering Section Ph. No. 8333853369/ executive engineer@manuu.edu.in before the date/time given in the online tender document / CPPP for seeking clarification.

Executive Engineer
MANUU, Hyderabad

INSTRUCTIONS FOR BIDDER

- 1. The intending bidder must carefully read the terms and conditions CPWD-6/7/8 as applicable for item rate contracts. He should only submit his bid if he considers himself eligible and he is in possession of all the documents required.
- 2. The contractor shall be a registered/enlisted contractor and should produce valid and definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings.
- 3. Contractors who fulfill the following requirements shall be eligible to apply.
 - (a) Should have satisfactorily completed the works as mentioned below during the last Seven years ending previous day of last date of submission of bids.

Three similar works each costing not less than Rs 10,04,038/-

or

Two similar works each costing not less than Rs 13,00,047/-

or

One similar work costing not less than Rs 20,80,075/-.

- 4. Only work completed and certified by competent authority of the organization will be accepted as experience certificate. Certificate not issued in the name of bidder (Contractor) or issued by an authority not competent to issue such certificate will not be accepted. Mere work order or purchase order etc., issued will not qualify for experience.
- 5. The copies of relevant certificates of income tax/IT returns, for the years 2018-19, 2019-20 and 2020-21 PAN Card, GST register certificated should accompany the technical bid.
- 6. Should have had average annual financial turnover not less than Rs. 7,80,028/- i.e., 30% of the estimated cost of the work during the last three years ending 31st March 2022.
- 7. To become eligible for issue of tender, the tenderer shall have to furnish an undertaking, as per Form 'J' affidavit at Annexure-V of this NIT.
- 8. Instructions for bidders posted on website shall form part of bid document.
- 9. The contractor submitting the bid should read the schedule of quantities, Special conditions, additional conditions, particular specifications and other terms and conditions given in the NIT. The bidder should also read the CPWD General Conditions of Contract for Works 2020 Maintenance with all correction slips issued up to the last date for submission of bid, which is available as a Government of India Publication and also can be seen on CPWD website (www.cpwd.gov.in). Where ever the following words appear in CPWD GCC, they may be read as follows:

	<u>For</u>	Read as
i.	CPWD	MANUU
ii.	Superintending Engineer	Registrar, MANUU
iii.	Divisional Officer	Executive Engineer, MANUU
iv.	Sub-Divisional Officer	Assistant Engineer (Civil), MANUU
V.	Engineer-in-Charge	Executive Engineer, MANUU
vi.	Director General (DGs)/SDG/ADG/	Vice-Chancellor/ Pro Vice-Chancellor, MANUU
	Chief Engineer	,

However, provisions included in the bid document shall prevail over the provisions contained in the standard form. The contractor should also visit the site of work and acquaint himself with the site conditions before Bidding.

- 10. Agreement shall be drawn with the successful tenderer in the prescribed Form No. CPWD 7/8 which is available in the University of Hyderabad website. Tenderer shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.
- 11. The time allowed for carrying out the work is 30 days from the date of start as defined in clause 5 Scheduled "F" or from the first date of handing over of the site, whichever is later, in accordance with phasing if any indicated in the tender document. The site shall be made available as and when required for execution of work.
- 12. Tenders shall be accompanied with Earnest money of 2% of estimated cost put to tender/fixed deposit receipt of a scheduled bank/demand draft/banker check of a scheduled bank issued in favour of Finance Officer, University of Hyderabad payable at Hyderabad.
- 13. The bid can only be submitted after submitting the EMD cover with original EMD in the office of Executive Engineer MANUU and uploading the mandatory scanned documents such as Insurance Surety Bonds, Account payee Demand Draft, Fixed Deposit Receipts and bankers Cheque or bank Guarantee from any of the commercial Banks or online payment in towards EMD in favour of Finance Officer, MANUU.
- 14. The Earnest Money in the form of Demand Draft or Banker's Cheque or Fixed Deposit Receipt, etc., drawn in favour of Finance Officer, MANUU, Hyderabad shall be scanned and uploaded to the etendering website(CPPP) within the period of bid submission. The original EMD should be deposited in the office of Executive Engineer, MANUU within the period of bid submission. The Executive Engineer shall issue a receipt of deposition of Earnest Money deposit to the bidder in a prescribed format.
- 15. The Bidder/contractor, whose tender is accepted, will be required to furnish performance guarantee of 3% (Three Percent) of the tendered amount (including the EMD amount) within the period specified in Schedule F. This guarantee shall be in the form of cash (in case guarantee amount is less than Rs. 10,000/-) or Deposit at Call receipt of any scheduled bank/Banker's cheque of any scheduled bank/Demand Draft of any scheduled bank/Pay order of any scheduled bank (in case guarantee amount is less than Rs. 1,00,000/-) Government Securities or Fixed Deposit Receipts or Guarantee Bonds of any Scheduled Bank in accordance with the prescribed form.

 In case the contractor fails to deposit the said performance guarantee within the period as indicated in Schedule "F" including the extended period if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor.
- 16. Performance Security is to be furnished within 7 days from the date of notification of the award and it should remain valid for a period of 60 (sixty) days beyond the date of completion of all contractual obligations of the contractor, including Defect Liability Period (DLP). This period can be further extended by Engineer-in-Charge up to a maximum period of 3 days on the written request of the contractor subject to payment of late fee @ 0.1% per day of Performance Guarantee amount.
- 17. The performance security will be forfeited and credited to the MANUU account in the event of a breach of contract by the contractor. It shall be refunded to the contractor without interest, after he duly performs and completes all obligations under the contract but not later than 365 days of completion of the Defect Liability Period (DLP).
- 18. GST on all materials as well as GST on Work Contract etc., or any other taxes applicable in respect of this contract shall be payable by the Contractor. Item rate quoted by him shall be indicated separately with GST component and Government will not entertain any claim for reimbursement whatsoever in respect of the same.
- 19. The quoted item rates of the contract shall be final and nothing extra shall be paid. Further the rates quoted by the contractor shall be inclusive of labour welfare cess and the same shall be recovered from the contractor's bills and will be remitted by the University as per relevant rule position, if any.

- 20. Bid Document consisting of specifications, the schedule of quantities of the various types of items to be executed and the set of terms and conditions of contract to be complied by the contractor whose bid may be accepted and other necessary documents can be seen in the office of the EE, MANUU between hours of 11.00 AM and 4.00 PM from 14.11.2022 to 22.11.2022 every day except on Saturday, Sunday and public Holidays or can be downloaded from website www.manuu.edu.in or www.eprocure.gov.in.
- 21. Contractor can upload documents in the form of JPG or PDF formats or as prescribed on CPPP.
- 22. Applicants are advised to keep visiting the above mentioned web-sites from time to time (till the deadline for bid submission) for any updates in respect of the tender documents, if any. Failure to do so shall not absolve the applicant of his liabilities to submit the applications complete in all respects including updates thereof, if any. An incomplete application may be liable for rejection.
- 23. The bidders enlisted under NSIC/MSME are requested to note that the present notice inviting tender is not for the "Supply of Goods", but for engaging a contractor under works contract. If bidders enlisted under NSIC/MSME are interested in participating in the tender, they may participate subject to fulfilment of the conditions of this notice inviting tender. However, they are exempted from paying EMD and previous experience. The 'Start-ups' as recognized by the Department of Industrial Policy and Promotion (DIPP) are also exempted from paying EMD and previous experience.
- 24. The description of the work is as follows: Copies of drawings and documents pertaining to the work will be open for referring/inspection by the tenderers at the office of above mentioned officer. Tenderers are advised to inspect and examine the site location and its area surroundings and satisfy themselves before submitting their tenders. The tenderer shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, required for executing the work including ward and watch unless otherwise services provided for in the contract documents.
- 25. Submission of required bid and all other tender documents by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done.
- 26. The competent authority on behalf of the MANUU does not bind itself to accept the lowest or any other tender and reserves to itself the authority to reject any or all the tenders received without the assignment of any reason. All tenders in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.
- 27. Canvassing whether directly or indirectly, in connection with tenderers is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.
- 28. The Executive Engineer on behalf of the competent authority of University reserves to himself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the rate quoted.
- 29. No Engineer of Gazette rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the previous permission of the Government of India in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as aforesaid before submission of the tender or engagement in the contractor's service.
- 30. The tender for the works shall remain open for acceptance for a period of thirty (30) days from the date of opening of tenders/Ninety days from the date of opening of financial bid. If any bidder withdraws his tender before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the tender which are not acceptable to the department, then the Government shall, without prejudice to any other right or remedy, be at liberty to

forfeit 50% of the said earnest money as aforesaid. Further the tenderer shall not be allowed to participate in the retendering process of the work.

- 31. The Contractor should furnish the contact telephone/cell phone numbers of self and their supervisor's to the institute. The working hours shall be from 9.00 am to 5.30 pm on all seven days of the week but if required, the Contractor should execute the works beyond the normal working hours/ as per therequirement of the institute.
- 32. The contractor liability for damage caused during installation work and imperfections; if the contractor or his / her workmen or servants shall break, deface, injure or destroy any part of the building in which they may be working or building road, fence, enclose, water pipe,cable,drain, electric or telephone posts or wires, trees, grass, or grasslands or any technical Equipment in the premises on which the work or any part of it as being executed, or if any defect, shrinkage or other faults appear in the work the contractor shall make good at his/ her own expense, or in default, the indenter may get the same rectified and deduct the expense from any amount that may be than due or at any time thereafter may become due to the contractor.
- 33. The successful tenderer/contractor, on acceptance of his tender by the Accepting Authority shall within 15 days from the stipulated date of start of the work, sign the contract consisting of:
 - a. The Notice Inviting Tender, all the documents including additional conditions, specifications and drawings, Clarifications if any, forming the tender as issued at the time of invitation of tender and acceptance thereof together with any correspondence leading thereto.
 - b. Standard C.P.W.D. Form 7/8
- 34. Time and Quality are the essence of this work and to ensure the same each R.A bill shall accompany timely, Quality, Quantity certificate and the same shallbe ensured by the Executive Engineer.
- 35. GST invoice form should be filled and submitted along with the bill.
- 36. The Labour engaged and working equipment brought by the contractor for the work shall be recorded in the MANUU Security main gate before entering in to the premises and obtain necessary gate pass.
- 37. The bid submitted shall become invalid if:
 - (i) The bidder is found ineligible.
 - (ii) The bidder does not deposit original EMD with the office of Executive Engineer, MANUU.
 - (iii) The bidder does not up loaded all the documents as stipulated in the bid document i.e., Copy of Registration/ enlistment order, Experience certificate, GST registration, PAN card and the scanned copy of EMD/Receipt issued by EE, MANUU.
 - (iv) If any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically by the lowest tenderer in the office of tender opening authority.
 - (v) If a bidder does not quote any percentage above/ below on the total amount of the tender, the tender shall be treated as invalid and will not be considered as lowest.
 - (vi) Bids on which any of the prescribed conditions is not fulfilled or any condition including that of conditional rebate is put forth by the bidders.
 - (vii) The lowest bidder does not deposit all the original documents (except those original documents already submitted) within a week **opening of tender**.
 - (viii) The Bidder does not furnish the Performance Guarantee of work as per NIT condition.
 - (ix). A Notarized Affidavit of 'Non-black listing' by CPWD/State/Central departments/PSU/Autonomous bodies as per Form "J" Not older than two months the date of Notice inviting tender.
- 38. All necessary licenses such as Labour license, EPFO and ESI, BOCW welfare registration etc., shall be taken by contractor within the time limits as prescribed under Clause 1 of Schedule- 'F'.

- 39. If any information furnished by the applicant is found to be incorrect at a later stage, he shall be liable to be debarred from Bidding/taking up of works in MANUU. The University reserves the right to verify the particulars furnished by the applicant independently.
- 40. The University reserves the right to accept or reject any prospective application without assigning any reason and to restrict the list of qualified contractors to any number deemed suitable by it, if too many bids are received satisfying the laid down criterion.
- 41. No bids shall be withdrawn in the interval between the last date of submission of bids and expiration of the period of bid validity.
- 42. While all efforts have been made to avoid errors in preparation of tender documents, the bidders are advised to check the same carefully. No claim on account of any error detected in the tender document shall be entertained.
- 43. At any time prior to the date of submission of bids, MANUU may, whether its own initiative or in response to a clarification sought by a prospective bidder, amend bid documents by using corrigendum which shall be notified on the MANUU official website.
- 44. Any dispute arising out of this Bid including dispute related to encashment of any Bank Guarantee/FDR etc., shall be subject to the jurisdiction of courts at Hyderabad only.
- 45. <u>List of Documents to be placed in the EMD cover and also to be scanned and uploaded in the e-Procurement portal within bid submission period:</u>
 - 1. Demand Draft/Pay order or Banker's Cheque / Deposit at Call Receipt/ FDR / Bank Guarantee of any Scheduled Bank against EMD in favour of "Finance Officer, MANUU, Hyderabad.
 - 2. Registration/Enlistment Order of the Contractor of appropriate class.
 - 3. Work experience certificate as per Para 3 above.
 - 4. Valid GST Registration for work contract.
 - 5. Copy of PAN card.

Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority.

Contact person of the Tender Inviting Authority:

Mr. S Nageswara Reddy, Executive Engineer (Phone 040 – 23008320/ Cell No. 8333853369)

POSTAL ADDRESS: OFFICE OF THE EXECUTIVE ENGINEER
Room No.15 & 16, Ground Floor, Administrative Building,
Maulana Azad National Urdu University, Gachibowli, Hyderabad-500032,
Telangana state. E-mail Id: executive engineer@ manuu.edu.in

Tender Application, Tender Submission and Tender Opening

The following Technical and Finance bid documents shall be upload simultaneously with scanned copies in e-procurement web site. The tender documents may also be seen at University of Hyderabad website-www.uohyd.ac.in

(A) Technical bid documents

- The Technical bid shall contain all the documents scanned and uploaded in the concerned wed site, based on which the bidder claim to be eligible as per eligibility criteria prescribed in NIT. Any discloser of finance bid in the technical bid documents will lead to summary rejection of bid.
- 2) Work experience certificates as per Eligibility criteria.
- 3) Contract registration certificate registered under State or Central Govt Departments or state/central autonomous bodies undertaking.
 - 4) PAN card & GST Registration Certificate.
 - 5) Latest TDS certificates for consecutive 3 years.
 - 6) Latest 3 years Turn over certificate.
 - 7) Undertaking as per Form "J".
 - 8) Other necessary documents as per Tender documents.
- 4) On the due date of opening, the Technical bid of those tender who furnished validEMD will only be opened. On opening of Technical bid, further detailed scrutiny/evaluation will be carried out. During the evaluation of techno commercial bids, the documents furnished by the tenderers will be scrutinized in detail.
- 5) Anytender, found as not fulfilling the eligibility criteria will be rejected at this stage and such offers will not be considered for further processing. The price bid of only those tenderers who have been qualified during the scrutiny and technical evaluation will be opened separately on a specified date (with due intimation to the qualified bidders) andfurther processed, as per tender procedure/stipulations.

MAULANA AZAD NATIONAL URDU UNIVERSITY

ITEM RATE BID & CONTRACT FOR WORKS

(A) Bid for the work of: -

<u>Name of Work</u>: For Construction of Silver Jubilee gate-II behind CIT building, MANUU Campus, Gachibowli, Hyderabad

- (i) <u>EMD Cover</u>: To be submitted by <u>15:00 Hrs on 22.11.2022</u> in the office of Executive Engineer, MANUU, Gachibowli, Hyderabad (Telangana State). <u>e-Bid</u>: To be submitted by <u>15:00 Hrs on 22.11.2022</u>
- (ii) To be opened in presence of qualified bidders / their authorized representatives who may be present at 15:0 Hrs on 23.11.2022 in the office of Executive Engineer, MANUU, Gachibowli, Hyderabad-500032.
- (iii) Agency:-.... (Contractor)

Executive Engineer,

Hyderabad (Telangana State).

BID

I/We have read and examined the notice inviting Bid, schedule, A, B, C, D, E & F Specifications applicable, Drawings & Designs, General Rules and Directions, Conditions of Contract, clauses of contract, Special conditions, Schedule of Rate & other documents and Rules referred to in the conditions of contract and all other contents in the Bid document for the work.

I/We hereby Bid for the execution of the work specified for the MANUU within the time specified in Schedule 'F' viz., schedule of quantities and in accordance in all respect with the specifications, designs, drawing and instructions in writing referred to in Rule-1 of General Rules and Directions and in Clause 11 of the Conditions of contract and with such materials as are provided for, by, and in respect of accordance with, such conditions so far as applicable.

We agree to keep the Bid open for thirty (30) days from the due date of its opening and not to make any modification in its terms and conditions.

A sum of Rs. 52,002/- is hereby forwarded in receipt treasury challan / deposit at call receipt of a scheduled bank / fixed deposit receipt of scheduled bank/demand draft of a scheduled bank as earnest money. If I/We, fail to furnish the prescribed performance guarantee within prescribed period. I/We agree that the said Vice-Chancellor, MANUU or his successors, in office shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/We fail to commence work as specified, I/We agree that Vice-Chancellor, MANUU or the successors in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said earnest money and the performance guarantee absolutely. The said Performance Guarantee shall be a guarantee to execute all the works referred to in the Bid documents upon the terms and conditions contained or referred to those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.3 of the Bid form. Further, I/We agree that in case of forfeiture of Earnest Money & Performance Guarantee as aforesaid. I/We shall be debarred for participation in the re-Bidding process of the work.

I/We hereby declare that I/We shall treat the Bid documents drawings and other records connected with the work as secret/confidential documents and shall not communicate information/derived there from to any person other than a person to whom I/We am/are authorized to communicate the same or use the information in any manner prejudicial to the safety of the State.

Dated:	Signature of Contractor
Witness:	Postal Address
Address:	
Occupation:	

ACCEPTANCE

	The above E	Bid (as modifie	ed by you as pro	vided in the letters	mentioned l	here under) is accepted by n	ne for
White the same	and on beha	lf of Registrar	, MANUU for a	sum of Rs		(Rupees	
)
	The letters r	eferred to belo	ow shall form pa	rt of this contract A	Agreement:-		
	(i)	~					
	(ii)						
	(iii)						
						Signature of Executive E	ngineer
	Dated:	1. 					
	Designation	:					

SCHEDULES

SCHEDULE 'A' Schedule of Quantities for Civil & Electrical (Enclosed)

SCHEDULE 'B'

Materials to be issued to the contractor: Nil

SCHEDULE 'C'

Tools and plants to be hired to the contractor: Nil

SCHEDULE 'D'

Extra schedule for specific requirements / documents for the work, if any: Nil

SCHEDULE 'E'

Reference to General Conditions of Contract:

GCC for CPWD Works 2020 Maintenance modified and amended up to the last date of submission of bid.

Name of work: Construction of 'Silver Jubilee Gate-II' behind CIT building, MANUU Campus, Gachibowli, Hyderabad

1.1. Estimated Cost Put to Bid

: Rs. 26,00,094/-

1.2. Earnest money

: Rs. 52,002/- (To be returned after receiving Performance

Guarantee).

1.3. Performance Guarantee

: 3% of accepted Bidded value

1.4. Security Deposit

: 2.5% of accepted Bidded value

SCHEDULE 'F'

General Rules & Directions:

Officer inviting Bid

Executive Engineer,
MANUU, Hyderabad
or successor thereof.
See below under Clause 12

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in : accordance with Clauses 12.2 & 12.3

Definitions

Engineer-in-Charge

Executive Engineer,

MANUU, Hyderabad or successor thereof.

Registrar,

MANUU, Hyderabad or successor thereof.

15%

Accepting Authority

Percentage on cost of materials and labour to cover all overheads and profits.

Standard schedule of Rates

DSR 2018 with up to date correction Slips /

amendments

Department/University

Engineering Section/ Maulana Azac National Urdu University

Standard CPWD contract Form

General Conditions of Contract 2020

Maintenance works as amended / modified up to last date of submission of Tender.

Clause 1

(i) Time allowed for submission of performance Guarantee/Programme Chart (Time and Progress) and applicable labour licenses, registration with EPFO, ESIC and BOCW Welfare Board or Proof of applying thereof from the date of issue of letter of acceptance 7 days

(ii) Maximum allowable extension with late fee at 0.1% per day of performance Guarantee amount beyond the period as provided in (i) above

3 days

Clause 2

Authority for fixing compensation under Clause-2.

Registrar,

MANUU, Hyderabad or successor thereof.

Clause 2A

Whether clause 2A shall be applicable

Not Applicable

Clause 5

Number of days from the date of issue of letter of

14 days

acceptance for reckoning date of start

or date of handing over of site whichever is later

Table of Mile Stone(s)

1	Description of Milestone	Time allowed in days(fromdate of start)	Amount to be with-held in case of non-achievement of mile stone
1	25% agreement value		In the event non-achieving the necessary progress as assessed from the running payments.
2	50% agreement	One half of time allowed for	2.5% of tendered value of work will be withheld for failure of each milestone.
3	75% agreement	Three fourth of time allowed for completion.	
4	100% agreement	Full period of time allowed for completion.	

Time allowed for execution of work30 days.....

(i) Extension of time

Executive Engineer, MANUU, Hyderabad.

(ii) Rescheduling of mile stones

Not applicable

(iii) Shifting the date of start in case of Delay in handing over of site

Executive Engineer, MANUU, Hyderabad.

Clause 6, 6A

i) For works having estimated cost more than Rs.15 lacs

Clause 6A

ii) For works having estimated cost Rs.15 lacs or less

Contractor's option either of clause 6 or Clause 6A (to be exercised at Tender

submission)

Clause 7

Gross work to be done together with net Payment / adjustment of advances for material collected, if any since the last such payment for being eligible to interim payment

Clause 7A

No Running Account Bill shall be paid for the work till the applicable labour licenses, Registration with EPFO, ESIC and BOCW Welfare Board, whatever applicable are submitted by the contractor to the Engineer-in-charge.

Whether Clause 7A shall be applicable Clause 10A

List of testing equipment to be provided by the contractor at site

Clause 10 B (ii)

Whether clauses 10 B (ii) shall be applicable

Clause 11

Specification to be followed for execution of work

Clause 12

Type of work: 12.2 & 12.3 Deviation limit beyond which clauses 12.2

& 12.3 shall apply for building work

(i) Deviation limit beyond which clauses 12.2 & 12.3 shall apply for foundation work (except earth work).

(ii) Deviation limit for items in earth work sub head of DSR or related items.

Clause 16

Competent Authority for deciding reduced rates

Clause 18

List of mandatory machinery, tools & plants to be deployed by the contractor at site

Clause: 25

Constitution of Dispute Redressal Committee (DRC)

Place of Arbitration

Clause: 31 Clause: 31 A

Clause: 51 A

Rs. 5.00 lakhs

Applicable.

Any equipment required at site as per item

of execution.

Not Applicable

CPWD specification latest Vol. I to II

amended upto date with up to date

correction slips.

ORIGINAL WORK.

Unlimited

Unlimited

Unlimited

Executive Engineer, MANUU, Hyderabad

As per requirement at site condition and

as per item of execution.

Applicable. If required, DRC shall be

appointed by Vice Chancellor, MANUU.

Hyderabad

Yes, Applicable

Not Applicable

Clause 36 Requirements of Technical Representative (s) and Recovery Rates:

SI. No.	Minimum Qualification of Technical Representative	Discipline	Designation (Principal Technical/ Technical representative)	Minimum experience	Number	Rate at which red be made from the inthe event of no provision of claus Mont h)	e contractor ot fulfilling se 36 (i) (per
1.	Graduate Engineer Or Diploma Engineer	Civil	Project Manager cum Planning / Quality / Site / Billing Engineer	2 Years Or 5 Years	1	Rs.15,000/-	Rupee s Fifteen Thousa nd Only.

Clause 42

(b)

(i) (a) Schedule / statement for determining theoretical quantity of cement & bitumen on the basis of Delhi Schedule of Rates 2016 printed by C.P.W.D with correction slips issued upto date.

Variations permissible on theoretical quantities.

(a) Cement for works with estimated cost put

to Bid not more than Rs. 5 lakhs

Cement for works with estimated cost put to Bid more than Rs. 5 lakhs

Bitumen for all works

Steel Reinforcement and structural steel (c)

sections for each diameter, section and category

3% plus/minus

2% plus/minus

2.5% plus only & nil on minus Side

2% plus/minus

(d) All other materials Nil

Terms & Conditions for Original & Maintenance Civil Work

- 1. The work shall be executed as per approved design and drawings, CPWD specifications latest, particular specifications, special conditions and the specifications of Bureau of Indian Standards. Where the aforesaid provisions and conditions are silent, relevant specialized literature and manufacturer's specification shall be followed for execution of work.
- Before tendering, the contractor shall inspect the site of work and shall fully acquaint himself about the
 conditions prevailing at site, availability of materials, availability of land and suitable locations for
 construction of godowns, stores and camp, transport facilities, the extent of leads and lifts involved in
 achieving the completion of work.
- 3. The contractor shall at his own expense and risk arrange land for accommodation of labour, setting up of office, the storage of materials, erection of temporary workshops, construction of approach roads to the site of the work including land required for carrying out of all jobs connected with the completion of the work. However, the departmental land, to the extent available may be allowed to be used for the purpose free of rent without accepting any responsibility for the delay, if any, on this account. The contractor shall have to abide by the regulations of the authorities concerned and the directions of the Officer-incharge for the use of the land available at the site of work. If during construction, it becomes necessary to remove or shift the stored materials shed workshop, access roads, etc, to facilitate execution of any other work by any other agency, the contractor shall carry out the removal of shifting as directed by the Officer-in-charge and no claim whatsoever, shall be entertained on this account.
- 4. It shall be deemed that the contractor has satisfied himself as to the nature and location of the work, transport facilities, availability of land for setting up of camp, etc. the department will bear no responsibility for lack of such knowledge & the consequences thereof.
- The contractor shall have to make approaches to site, if so required and keep them in good condition for transportation of labour and materials as well as inspection of works by the Officer-in-charge. Nothing extra shall be paid on this account.
- 6. Materials used on work without prior approval and testing (where testing is necessary) by the Officer-in-charge are liable to be considered unauthorized, and not acceptable. The Officer-in-charge shall have full powers for removal of any or all of the materials brought to site by contractor which are not in accordance with the contract specifications or do not conform, in character or quality to the samples approved by the Officer-in-charge. In case of default on the part of the contractor in removing rejected materials, the Officer-in-charge shall be at liberty to have them removed at the risk and cost of the contractor.
- 7. The work shall be carried out in such a manner so as not to interfere / or adversely / or disturb other works being executed by other agencies, if any.
- 8. Any damage done by the contractor to any existing work or work being executed by other agencies shall be made good by him at his own cost.
- 9. The contractor shall maintain in good condition all work executed till the completion of entire work entrusted to the contract under this contract.
- 10. No payment shall be made to the contractor for damage caused by rain, flood and other natural calamities whatsoever during the execution of works and any damage to the work on this account shall have to be made good by the contractor at his own cost.
- 11. Unless otherwise specified in the Scheduled of Quantities, the Rates of all the items of the work shall be considered as inclusive all charges like Transportation, Royalty and other Taxes etc.
- 12. The Contractor shall take instructions from the Officer-in-charge regarding collections and stacking of materials at site.
- 13. The Contractor shall be responsible to arrange at his own cost all necessary Tools and plants required for execution of original and maintenance works.
- 14. The contractor shall make his own arrangements for obtaining Electric connection, if required and make necessary payment directly to the Department concerned.

- 15. Water for executing the work will have to be arranged by the Contractor and not to depend on MANUU directly or indirectly.
- 16. The operating cost of contractors machinery at site i.e. Petrol/ Kerosene Oil/ Mobile Oil etc, and proper repair and maintenance of Lawn Mowers and Pumps shall be borne by the contractor himself.
- 17. The Department shall not be responsible for any injury partial or permanent or death of any workers at site due to accident or malfunctioning of the equipment or by negligence of the Contractors staff on site.
- 18. No compensation shall be payable to the Contractor for any damage caused by rains, storms, earthquakes and other calamity during the execution of work.
- 19. All applicable and prevailing taxes will be recovered from the contractor bills as applicable from time to time.
- 20. If any damage caused for public conveniences/ services, the same shall have to be repaired instant, failing which necessary recovery shall be make from the Contractors bill.
- 21. If any Building, Road and Channels will be damaged by the Contractor the same will have to repair by the Contractor at his risk and cost, otherwise the complete cost will be recovered as intimated by the Engineer-in-charge.

Form of Earnest Money (Bank Guarantee)

WHEREAS, contractor (Name of contractor) (hereinafter called "the contractor") has submitted his Bid dated
KNOW ALL PEOPLE by these presents that we
SEALED with the Common Seal of the said Bank this day of
THE CONDITIONS of this obligation are:
If after Bid opening the Contractor withdraws, his Bid during the period of validity of Bid (including extended validity of Bid) specified in the Form of Bid; If the contractor having been notified of the acceptance of his Bid by the Engineer-in-Charge:
fails or refuses to execute the Form of Agreement in accordance with the Instructions to contractor, if required; OR fails or refuses to furnish the Performance Guarantee, in accordance with the provisions of Bid document
and Instructions to contractor,
We undertake to pay to the Engineer-in-Charge either up to the above amount or part thereof upon receipt of his first written demand, without the Engineer-in-Charge having to substantiates his demand, provided that in his demand the Engineering- Charge will note that the amount claimed by his is due to him owing to the occurrence of one or any of the above conditions, specifying the occurred condition or conditions.
This Guarantee will remain in force up to and including the date*
DATE

19

Form of Performance Guarantee / Bank Guarantee Bond

	In consideration of the Vice-Chancellor, MANUU(hereinafter called "The University") having agreed under the terms and conditions of agreement No
	(hereinafter called "the said contractor(s)") for the work
	(herein after called "the said
	Agreement") having agreed to production of a irrevocable Bank Guarantee for Rs
	only) as security/guarantee from the contractor(s) for
	compliance of his obligations in accordance with the terms and conditions in the said agreement.
	We, hereinafter referred to as "the Bank")
((Indicate the name of the Bank)
	hereby undertake to pay to the University an amount not exceeding Rs. Only) on demand
	by the University.
	We do hereby undertake to pay the amounts
5	We do hereby undertake to pay the amounts (Indicate the name of the Bank)
	due and payable under this Guarantee without any demure, merely on a demand from the Government stating that the amount claimed is required to meet the recoveries due or likely to be due from the said
	contractor(s). Any such demand made on the Bank shall be conclusive as regards the amount due and
	payable by the Bank under this Guarantee. However, our liability under this guarantee shall be restricted to an amount not exceeding
	Rs (Runees
	only).
	We, the said Bank further undertake to pay to the University any money so demanded notwithstanding my dispute or disputes raised by the contractor(s) in any suit or proceeding pending before any court or Tribunal relating thereto, out liability under this present being absolute and unequivocal. The payment so made by us under this bond shall be valid discharge of our liability for payment there
	under and the contractor(s) shall have no claim against us for making such payment.
r	We further agree that the guarantee herein (Indicate the name of the Bank)
	contained shall remain in full force and effect during the period that would be taken for the performance of the said agreement and that it shall continue to be enforceable till all the dues of the
	University under or by virtue of the said agreement have been fully paid and its claims satisfied or discharged or till Engineer-in-charge on behalf of the University certified that the terms and
	conditions of the said agreement have been fully and properly carried out by the said contractor(s) and accordingly discharges this guarantee.
С	We further agree with the University (Indicate
	the name of the Bank) that the University shall have the fullest liberty without our consent and without effecting in any manner our obligations here under to vary any of the terms and conditions of the said agreement or to extend time of performance by the said contractor(s) from time to time or to postpone for any time or from time to time any of the powers exerciseble by the Government against
	the said contractor(s) and to for-bear or enforce any of the terms and conditions relating to the said agreement and we shall not be relieved from our liability by reason of any such variation, or extension
	being granted to the said contractor(s) or for any forbearance, act of omission on the part of the Government or any indulgence by the Government to the said contractor(s) or by any such matter or thing whatsoever which under the law relating to sureties would, but for this provision, have effect of so relieving us.

	6.	This guarantee will not be discharged due to the change in the constitution of the Bank or the contractor(s).
er a enforcement or some	7.	We lastly undertake not to revoke this (Indicate the name of the Bank) guarantee except with the previous consent of the University in writing.
5 5 -24min (20)	8.	This guarantee shall be valid up to unless extended on demand by Government. Notwithstanding any mentioned above, our liability against this guarantee is restricted to Rs (Rupees only) and unless a claim in writing is lodged with us within six months of the date of expiry or the extended date of expiry of this guarantee all our liabilities under this guarantee shall stand discharged.
		Dated the day of for (Indicate the name of the Bank).

Sample letter for Acceptance of Bid

By Registered Post

No.	Dated:
То	(Name and Address of the contractor)
Subje	(Name of work as appearing in the Bid for the work).
Dear S	Sir(s)
	Your Bid for the work mentioned above has been accepted on behalf of the Vice-Chancellor, MANUU at your Bided / negotiated Bid amount of Rs
1.	You are requested to submit the performance guarantee of Rs
2.	Please note that the time allowed for carrying out the work as entered in the Bid days, will be reckoned from days subject to maximum allowable extension under Clause 1(ii), from the date of issue of this letter.
	Yours faithfully,
	Registrar For & on behalf of Hon'ble Vice-Chancellor, MANUU

Sample letter for Commencement of works

By Registered Post

No.		Date:
То		
		(Name and Address of the contractor)
Subject	t:	(Name of work as appearing in the Bid for the work).
Ref:		1. Performance guarantee submitted by you vide your letter No Dated for above work.
		2. This office letter of intent/ acceptance of Bid Nodt
Dear S	ir(s)	
		continuation to the letters referred above, you are requested to attend this office to complete formatement within 15 days from stipulated date of start.
	poss Bid be r	a are requested to contact the Executive Engineer, MANUU, Gachibowli, Hyderabad for taking session of site and starting the work on or before days from the date of letter of acceptance of a Please note, that the time allowed for carrying out the work as entered in the Bid () days, will reckoned from to days subject to maximum allowable extension under Clause 1(ii), from date of issue of acceptance letter
		Yours faithfully,
		Executive Engineer For & on behalf of Registrar, MANUU

FORM 'J' AFFIDAVIT

I/we undertake and confirm that our firm/partnership firm has not been blacklisted by any state/Central Departments/PSUs/Autonomous bodies during the last 7 years of its operations. Further that, if such information comes to the notice of the department then I/we shall be debarred for bidding in CPWD in future forever. Also, if such information comes to the notice of department on any day before date of start of work, the Engineer-incharge shall be free to cancel the agreement and to forfeit the entire amount of Earnest Money Deposit/Performance Guarantee (Scanned copy of this notarized affidavit to be uploaded at the time of submission of bid)

NOTE: Affidavit to be furnished on a 'Non-Judicial' stamp paper worth Rs.100/-

Signature of Bidder(s) or an authorized

Officer of the firm with stamp

Signature of Notary with seal

INTEGRITY PACT

	(Name of the bidder)	
Ci.,		
OII.		

To:

Sub.: Notice inviting e-tenders No. MANUU/Engg/2022-23/001, dated 10-11-2022 for the work of "Construction of 'Silver Jubilee Gate-II' behind CIT building, MANUU Campus, Gachibowli, Hyderabad

It is hereby declared that MANUU, Hyderabad is committed to follow the principles of transparency, equity and competitiveness in public procurement.

The subject Notice Inviting Tender (NIT) is an invitation to offer made on the condition that the bidder will sign the Integrity Agreement, which is an integral part of tender/bid document, failing which the tenderer/bidder will stand disqualified from the tendering process and the bid of the bidder would be summarily rejected.

This declaration shall form part and parcel of the Integrity Agreement and signing of the same shall be deemed as acceptance and signing of the Integrity Agreement on behalf of the MANUU, Hyderabad.

Yours sincerely

Executive Engineer, MANUU, Hyderabad.

To:
Registrar,
MANUU
Gachibowli
Hyderabad-500 032

Sir,

Sub: Construction of 'Silver Jubilee Gate' behind CIT building, MANUU Campus, Gachibowli, Hyderabad

I/We acknowledge that MANUU, Hyderabad is committed to follow the principles thereof as enumerated in the Integrity Agreement enclosed with the tender/bid document.

I/We agree that the Notice Inviting Tender (NIT) is an invitation to offer made on the condition that I/We will sign the enclosed integrity Agreement, which is an integral part of tender document, failing which I/We will stand disqualified from the tendering process. I/We acknowledge that THE MAKING OF THE BID SHALL BE REGARDED AS AN UNCONDITIONAL AND ABSOLUTE ACCEPTANCE of this condition of the NIT.

I/We confirm acceptance and compliance with the Integrity in letter and spirit and further agree that execution of the said Integrity Agreement shall be separated and distinct from the main contract, which will come into existence when tender/bid is finally accepted by MANUU, Hyderabad. I/We acknowledge and accept the duration of the Integrity Agreement, which shall be in the line with Article 1 of the enclosed Integrity Agreement.

I/We acknowledge that in the event of my / our failure to sign and accept the Integrity Agreement, while submitting the tender/bid, MANUU, Hyderabad shall have unqualified, absolute and unfettered right to disqualify the tenderer/bidder and reject the tender/bid in accordance with terms and conditions of the tender/bid.

Yours faithfully,

Date:

(Duly authorized signatory of the Bidder) Seal and signature of the contractor.

INTEGRITY PACT AGREEMENT

This Integrity Agreement is made at Hyderabad on this
BETWEEN
Maulana Azad National Urdu University, Hyderabad, represented through the Registrar, MANUU, Hyderabad (hereinafter referred as the 'Principal/Owner', which expression shall unless repugnant to the meaning or context hereof include its successors and permitted assigns)
AND
(Name and Address of the Individual/firm/Company)
Through
"Bidder/Contractor" and which expression shall unless repugnant to the meaning or context hereof include its succession and permitted assigns)
Preamble
WHEREAS THE Principal / Owner has floated the Tender (No. MANUU/ENG/Tender-1/02020-21/Hyd dated 07-12-2020) (Hereinafter referred to as "Tender/Bid") and intends to award, under laid down organizational procedure, contract for "Silver Jubilee Gate-II' behind CIT building, MANUU Campus, Gachibowli, Hyderabad"
[Hereinafter referred to as the "Contract").

AND WHEREAS the Principal/Owner values full compliance with all relevant laws of the land, rules, regulations, economic use of resources and of fairness/transparency in its relation with its Bidder(s) and Contractor(s).

AND WHEREAS to meet the purpose aforesaid both the parties have agreed to enter into this Integrity Agreement (hereinafter referred to as "Integrity Pact" or "Pact"), the terms and conditions of which shall also be read as integral part and parcel of the Tender/Bid documents and Contract between the parties.

NOW, THEREFORE, in consideration of mutual covenants contained in this Pact, the parties hereby agree as follows and this witnesses as under:

Article 1: Commitment of the Principal/Owner

- i. The Principal /Owner commits itself to take all measures necessary to prevent corruption and to observe the following principles:
 - (a) No employee of the Principal /Owner, personally or through any of his/her family members, will in connection with the Tender, or the execution of the Contract, demand, take a promise for or accept, for self or third person, any material or immaterial benefit which the person is not legally entitled to.

- (b) The Principal /Owner will, during the Tender process, treat all Bidder(s) with equity and reason. The Principal /Owner will, in particular, before and during the Tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential / additional information through which the Bidder(s) could obtain an advantage in relation to the Tender process or the Contract execution.
- (c) The Principal /Owner shall endeavour to exclude from the Tender process any person, whose conduct in the past has been of biased nature.
- ii. If the Principal /Owner obtains information on the conduct of any of its employee which is a criminal offence under the Indian Penal code (IPC)/Prevention of Corruption Act, 1988 (PC Act) or is in violation of the principles herein mentioned or if there be a substantive suspicion in this regard, the Principal /Owner will inform the Chief Vigilance Officer and in addition can also initiate disciplinary actions as per its internal laid down policies and procedures.

Article 2: Commitment of the Bidder(s)/ Contractor(s)

- 1) It is required that each Bidder/Contractor (including their respective officers, employees and agents) adheres to the highest ethical standards, and report to the Government / Department all suspected acts of **fraud or corruption or Coercion or Collusion** of which it has knowledge or becomes aware, during the tendering process and through the negotiation or award of a contact.
- 2) The Bidders(s)/Contractor(s) commit himself to take measures necessary to prevent corruption. He commits himself to observe the following principles during his participation in the Tender process and during the Contact execution:
 - a. The Bidders(s)/Contractor(s) will not, directly or through any other person or firm, offer, promise or give to any of the Principal/Owner's employees involved in the Tender process or execution of the Contract or to any third person any material or other benefit which he/she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the Tender process or during the execution of the Contractor.
 - b. The Bidders(s)/Contractor(s) will not enter with other Bidders(s) in to any undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to cartelize in the bidding process.
 - c. The Bidders(s)/Contractor(s) will not commit any offence under the relevant IPC/PC Act. Further the Bidders(s)/Contractor(s) will not use improperly, (for the purpose of competition or personal gain), or pass on to others, any information or documents provided by the Principal/Owner as part of the business relationship, regarding plans, technical proposals and business details, including information contained or transmitted electronically.
 - d. The Bidders(s)/Contractor(s) of foreign origin shall disclose the names and address of agents/representatives in India, if any. Similarly Bidder(s)/Contractor(s) of Indian Nationality shall disclose names and address of foreign agents/representatives, if any. Either the Indian agent on behalf of the foreign principals or the foreign principal directly could bid in a tender but not both. Further, in cases where an agent participates in a tender on behalf of one manufacturer, he shall not be allowed to

quote on behalf of another manufacturer along with the first manufacturer in a subsequent/parallel tender for the same item.

- e. The Bidders(s)/Contractor(s) will, when presenting his bid, disclose (with each tender as per proforma enclosed) any and all payments he has made, is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the Contract.
- iii. The Bidders(s)/Contractor(s) will not, instigate third persons to commit offences outlined above or be an accessory to such offences.
- iv. The Bidders(s)/Contractor(s) will not, directly or through any other person or firm indulge in fraudulent practice means a wilful misrepresentation or omission of facts or submission of fake/forged documents in order to induce public official to act in reliance thereof, with the purpose of obtaining unjust advantage by or causing damage to justified interest of others and/or to influence the procurement process to the detriment of the Government interests.
- v. The Bidders(s)/Contractor(s) will not, directly or through any other person or firm use Coercive practices (means the act of obtaining something, compelling an action or influencing a decision through intimidation, there or the use of force directly or indirectly, where potential or actual injury may befall upon a person, his/her reputation or property to influence their participation in the tendering process).

Article 3: Consequences of Breach

Without prejudice to any rights that may be available to the Principal/Owner under law or the Contract or its established policies and laid down procedures, the Principal/Owner shall have the following rights in case of breach of this Integrity Pact by the Bidders(s)/Contractor(s) and the Bidders/Contractor accepts and undertakes to respect and uphold the Principal/Owner's absolute right:

- 1) If the Bidders(s)/Contractor(s), either before awarded or during execution of Contract has committed a transgression through a violation of Article 2 above or in any other form, such as to put his reliability or credibility in question, the Principal/Owner after giving 14 days' notice to the contractor shall have powers to disqualify the Bidders(s)/Contractor(s) from the Tender process terminate/determinate the Contract - if already executed, or exclude Bidders/Contractor from future contract award processes. The imposition and duration of the exclusion will be determined by the severity of transgression and determined by the Principal/Owner. Such exclusion may be forever or for a limited period as decided by the Principal/Owner.
- Principal/Owner has disqualified the Bidders(s) from the tender process prior to the award of the Contract or terminate/determinate the Contract or has accrued the right to terminate/determinate the Contract according to Article 3(1), the Principal/Owner apart from exercising any legal rights that may have accrued to the Principal/Owner, may in its considered opinion forfeit the entire amount of Earnest Money Deposit, Performance Guarantee and Security Deposit of the Bidders/Contractor.
- 3) Criminal Liability: If the Principal/Owner obtains knowledge of conduct of a Bidder or Contractor, or of an employee or a representative or an associate of a Bidder or Contractor which constitutes corruption within the meaning of Indian Penal code (IPC)/Prevention of Corruption Act, or if the Principal/Owner has

substantive suspicion in this regard, the Principal/Owner will inform the same to law enforcing agencies for further investigation.

Article 4: Previous Transgression

- 1) The Bidder declares that no previous transgressions occurred in the last 5 years with any other Company in any country conforming to the anticorruption approach or with Central Government or State Government or any other Central/State Public Enterprises in India that could justify his exclusion from the Tender process.
- 2) If the Bidder makes incorrect statement on this subject, he can be disqualified from the Tender process or action can be taken for banning of business dealings/ holiday listing of the Bidder/Contractor as deemed fit by the Principal/Owner.
- 3) If the Bidder/Contractor can prove that he has resorted / recouped the damage caused by him and has installed a suitable corruption prevention system, the Principal/Owner may, at its own discretion, revoke the exclusion prematurely.

Article: 5 Equal Treatment of all Bidder/Contractors/Subcontractors

- 1) The Bidders(s)/Contractor(s) undertake(s) to demand from all subcontractors a commitment in conformity with this Integrity Pact. The Bidders/Contractor shall be responsible for any violation(s) of the principles laid down in this agreement/Pact by any of its Subcontractors/sub-vendors.
- 2) The Principal/Owner will enter into pacts on identical terms as this one with all Bidders and Contractors.
- 3) The Principal/Owner will disqualify Bidders, who do not submit, the duly signed pact between the Principal/Owner and the bidder, along with the Tender or violate its provisions at any stage of the Tender process, from the Tender process.

Article 6: Duration of the Pact

This Pact begins when both the parties have legally signed it. It expires for the Contractor/Vendor 12 months after the completion of work under the contractor or till the continuation of defect liability period, whichever is more and for all other bidders, till the Contract has been awarded.

If any claim is made/lodged during the time, the same shall be binding and continue to be valid despite the lapse of this pacts as specified above, under it is discharged/determined by the Competent Authority of MANUU, Hyderabad.

Article 7: Other Provisions

- 1) This Pact is subject to Indian Law, place of performance and jurisdiction is **Hyderabad**, the Headquarters of the Principal/Owner, who has floated the Tender.
- 2) Changes and supplements need to be made in writing. Side agreements have not been made.

- 3) If the Contractor is a partnership or a consortium, this Pact must be signed by all the partners or by one or more partner holding power of attorney signed by all partners and consortium members. In case of a Company, the Pact must be signed by a representative duly authorized by board resolution.
- 4) Should one or several provisions of this Pact turn out to be invalid; the remainder of this Pact remains valid. In this case, the parties will strive to come to an agreement to their original intensions.
- 5) It is agreed term and condition that any dispute or difference arising between the parties with regard to the terms of this Integrity Agreement / Pact, any action taken by the Owner/Principal in accordance with this Integrity Agreement / Pact or interpretation thereof shall not be subject to arbitration.

Article 8: LEGAL AND PRIOR RIGHTS

Place: Hyderabad.

Dated:

All rights and remedies of the parties hereto shall be in addition to all the other legal rights and remedies belonging to such parties under the Contract/ or law and the same shall be deemed to be cumulative and not alternative to such legal rights and remedies aforesaid. For the sake of brevity, both the Parties agree that this Integrity Pact will have precedence over the Tender/Contract documents with regard any of the provisions covered under this Integrity Pact.

IN WITNESS date first above	WHEREOF the parties have signed and executed this Integrity Pact at the place and e mentioned in the presence of following witnesses:
***************************************	,
(For and on be	half of Principal/Owner)
	······································
(For and on be	half of bidder/ contractor)
WITNESSES:	
1.	(Signature, name and address)
2.	
	(Signature, name and address)

<u>Special conditions regarding contractor's obligations under Employees'</u> <u>Provident Fund (EPF) and Employees' State Insurance (ESI) Acts.</u>

The contractor must comply with all his obligations under EPF and ESI Acts and Rules. The contractor shall indemnify the Institute of any recovery against non-compliance with the EPF and ESI Acts and Rules.

Indemnity by the contractor:

"I/ We hereby indemnify the Maulana Azad National Urdu University, Hyderabad (represented by its Registrar) that in case of any notice served by the EPF and/ or ESI authorities to the Institute towards recovery of EPF and/ or ESI due from me/ us in connection with this contract, I/ we agree that the Institute is free to recover such many as decided by the Institute from my bills or any money due to me from the Institute".

In case, notice is received by the Institute for non-compliance and/ or non-payment of EPF and / or ESI contribution from the contractor, the same shall be deducted from any money due to the contractor.

Seal and signature of the contractor.

Special conditions regarding contractor's obligations under MINES & Quarries –The Telangana State Minor Mineral Concession Rules, 1966 and amendments Go No. 37 dated 26.07.2016 regarding purchasing minor minerals from the licensed agencies.

The contractor shall deposit royalty and obtain necessary permit for supply of minor minerals and building materials, red bajri, stone, kankar, etc. from local authorities/ Department of Mines and Geology and produce the documents/ Mineral Dispatch Permits (MDPs) in this regard. However, the contractor shall also purchase minor minerals and building materials required for the work from private sources like quarry lease holders or private quarry owners licensed under Telangana MMC Rules 1966 duly remitting royalty charges and produce the documents/ MDPs in this regard.

Failing to this, recovery towards royalty charges will be made at fifteen times the tariff fixed by the Government.

Seal and signature of the contractor.

LIST SHOWING PREFERRED BRANDS/MANUFACTURERS/MAKE

- 1) A List of Preferred Brand Names of Various Materials / Products are shown below for usage in execution of Work. However, Approved equivalent material of any other Specialized Companies / Firms may also be used, in case it is established that the Brands Specified below are not available in the market and subject to Approval of the alternate Brand by the Engineer In charge.
- 2) It must be ensured, in general, that all materials to be used in the works shall bear BIS Certification mark. In cases where for a particular material/product, BIS Certification Mark is not available, then the material proposed to be procured can be used subject to the condition that it should conform to CPWD Specifications and relevant BIS codes. In such cases written approval of the Engineer-in -Charge shall be obtained before use of such material in their works.
- 3) The list given below does not absolve the Executing Agency from their responsibility for using these products. It is only after, they are satisfied about the quality and performance, the products shall be used. To achieve this, proper check on the quality of the product, actually to be used, should be exercised.

S.No	Product	Make
1	Ordinary Portland Cement	ACC, Ultratech, Vikram, Shree Cement, Ambuja, Jaypee Cement, Century Cement, JK Cement, Penna Cement, Bharathi Cement, Maha, Nagarjuna and Brands Approved by CE(SZ)II,CPWD,Hyderabad.
2	White Cement	Birla, J.K. White, Travancore
3	Reinforcement steel – (Primary Producers)	RINL, SAIL, TATA STEEL Ltd., JSW STEEL Ltd., JINDAL STEEL & POWER Ltd., Shyam produced by M/s.Shyam Steel Industries Ltd and Manufacturers approved by Spl.DG(SR),CPWD,Chennai
4	Ready Mix Concrete (RMC)	Ultra Tech, ACC, RMC Ready Mix (India), Nuvoco Vistas Corporation Ltd., (formally known as Lafarge India Ltd.), RMC by M/s Aparna Enterprises limited, Hyderabad, RDC Concrete (India) Pvt. Ltd and additional firms approved by CE, SZ-II, CPWD, Hyderabad.
5	Pulverized Stone Sand/ Crushed Stone Sand (Manufactured Sand)	Rank Enterprises, Robo Sand.
6	Polymer based Curing Compounds	FOSROC, SIKA, BASF
7	Structural Steel Sections	TATA, SAIL,RINL, JINDAL Steel & Power Ltd., J SW
8	Hollow Steel Tube Sections	TATA, Jindal, Apollo
9	Fly ash Cement Bricks	KSP Industries, Prakash International Ltd,
10	Autoclaved Aerated Concrete Blocks (AAC)	M/s. Hyderabad Industries Ltd., M/s. Ultra Tech India Limited, M/s. Siporex India Ltd., NCL, NUBRIC.
11	Binding Wire	TATA, JSW
12	Factory Made Cement Concrete Cover Blocks	A.S.R. Cover Blocks, Stand alone Universal Concrete Cover Blocks
13	RCC Door Frames	Ventura, Bothra.

14	Flush Door Shutters	Raavela Doors, Indian Timber Products,
	~ + 4	Kitply,
15	Fire Check / Rated Doors	Navair, Godrej, Shaktimet, Kenwood, MPP Schodders.
16	Smoke Seal Strip	Promat, Astro flame
17	Plain / Prelaminated Particle Board	ECO Board, TESA Action Co., Kitlam, Archid ply, Century
18	Ply wood / Laminate	Kitply, Centuryply, Greenply, Merino, Sonear (Donear), Formica, Archidply, Royal touch.
19	Natural wood Veneers	Kitply, Centuryply, Sonear (Donear), Greenply Archidply, Durain, National Action Tesa, Anchor.
20	Adhesive / Glue	Pidilite, Dunlope, Sika, Fosroc, Vamorganic.
21	Steel Windows/ Pressed Steel Frames	Madhu Industries, (Bengaluru), San Harvic, NCL
22	Cement Bonded Particle Board	BISON Boards of NCL.
23	PVC Door Frames & Shutters	Rajshri Plastiwood, Sintex.
24	FRP Door Frames & Shutters	Meena Fibre Glass, Duroplast, Cactus, Polyline.
25	UPVC Windows	Fenesta, Kommerling, Rehau, Wintech, LG, Encraft – Madhu Industries, Polywood.
26	Ceramic Floor /Dado Tiles	Somany, Johnson, Kajaria, Orient, Bell, RAK, Asian, NITCO, AGL tiles.
27	Vitrified Tiles	Somany, Johnson, Kajaria, Orient Bell Ltd, RAK, Vitero brand Aparna tiles
28	Precast Terrazo Tiles	NITCO, Hindustan, Modern
29	Precast Chequered Tiles	NITCO, Hindustan, INDO, Bharat, Poddar.
30	Non Metallic Floor Surface Hardners	Ironite, Hardonite, FOSROC, SIKA, BASF, CICO, Pidilite.
31	Precast Cement Concrete Tiles	NITCO, Hindustan, INDO, Ultra, NTC, Poddar.
32	Factory made Cement Concrete Interlocking Paver Blocks	Earth Pavers Hyd. Pvt. Ltd., NITCO (Rockard), Bharat (Nilsan), Classic Tiles.
33	Grass Paver	Unistone, Ultra.
34	Glass Mosaic Tiles	Palladio, Coral, Mridul, Bisazza
35	PVC Flooring	LG Hausys, Ger Flor, Armstrong.
36	High Density Fibre (HDF) Pre-laminated Flooring boards	Pergo, Armstrong.
37	Unglazed Heavy Duty Vitrified Tiles	Somany (Dura Gres), Kajaria (Pavigres).
38	Unglazed Heavy Duty Paver/Parking Tiles	Somany (Dura Stone), Johnson (Endura),

39	Clay Tiles on Roof	Kenjai, Johnson, Common Wealth Trust (Ind) Ltd
40	Tile Adhesives	Laticrete, ,Ardex Endura, Weber, Roff. SIKA, Ferrous.
41	Grout Compound/ Epoxy Grouts	Laticrete, Ardex Endura, Weber, Fosroc,
42		Pidilite, SIKA, Ferrous, BASF, CICO.
43	Water Proofing Compound	Fosroc, CICO, SIKA, Pidilite, .
Epox		Fosroc, CICO, SIKA, Pidilite, , BASF,
У		Accoproof, Ardex Endura.
Moto		1 ,
r		
Fosrc		
c, SIKA		
SIKA		
BAS		
44	Damp Proof Material	Duraseal, Acco-proof, Impermo
45	Actactic Polypropylene (APP) Modified Water	S T P, Bitumat Co. Ltd., Pidilite, Hydrotech
	Proof Membrane	Ltd.
46	Admixtures / Platisizers	Fosroc, CICO, SIKA, BASF, MC
47	Ethylene Propylene Diene Monomer (EPDM) Gasket	Hanu /Anand
48	Aluminium Extruded sections	Jindal, Hindalco, Indian Aluminium Co.
49	Polyester Powder Coating	Nerolac, Berger, Akzonobel, Jotun
50	Poly Sulphide Sealant	Pidilite, Tuffseal, Choksey chemicals.
51	Cement Based Wall putty	Birla Wall Care, J.K. Wall putty, Berger Paints, Asian Paints.
52	Paints/ Primer / Acrylic Emulsion (Premium Quality)	ICI Dulux, Asian Paints, Berger, Nerolac .
53	Melamine Polish	Asian Paints, Melamyne Gold Wudfin of Pidilite Industries, Timbertone of ICI Dulux.
54	Water Proofing Cement Paint	Snowcem India, ICI Dulux, Berger, Asian.
55	PU Enamel Metallic Paints on MS Structure & Epoxy paints (Premium Quality)	SKK, Akzonobel, Asian, Berger, MRF.
56	Calcium Silicate False Ceiling Tiles	A anglita Ca. Hilaan A
57	Gypsum Board False Ceiling Tiles	Aerolite Co, Hilux, Armstrong Saint Gobain, Lafarge, Amstrong Co.
58	Mineral Fibre Board False Ceiling Tiles	
59	Rockwool / Glasswool insulation.	Armstrong, Decosonic. Twigafiber, Llyod Insulation, Supreme.
	False Flooring System .	Kebao, Pinnacle, Access Floor System
61	Anodised / Powder Coated Aluminium Fittings /	Everite, Jyoti, Shakti, Sigma (BIS mark),
	Fixtures-	Hardima.
62	Stainless Steel Pipes (Railing)	Jindal Stainless Steel Ltd., Connect

		Architectural Products Pvt. Ltd.
63	Stainless Steel Wire Mesh	Champion Make, GKD.
64	Float / Plain / Tinted / Tempered / Toughened Glass.	Modi, Saint Gobain, Asahi, Atul, Glaverbel, Pilkington.
65	Mirror Glass.	Modi Guard, Atul, Asahi, Goldenfish.
66	Hydraulic Door Closers / Floor Springs	Godrej, Hardwyn, Everite, Dorma, Dorset, Magnum, Kich.
67	Steel Nuts, Bolts and Screws-	Atul, Hilti, Kundan, Priya.
68	Ball Bearing Hinges and Spring Hinges	Dorma, Hafele, Geze, Dorset, Magnum.
69	Stainless Steel Screws	Kundan, Arrow, Nettlefold, GKW.
70	Clamping System Using Dash / Anchor Fastners.	Hilti, Fischer, Bosch, Canon.
71	Locks in Furniture Cabinets.	Hettich, Blum, Hafel, Godrej, Link, Harrison.
72	Four Point / Multi Point Locking Handle.	Hefele, Alu-Alfa, Geze, Dorma, Godrej.
73	Stainless Steel Friction stay hinges	Hafele, Earl Bihari
74	Door closer lock / Panic exit device	Ingersoll Rand, Dorma, Monarch.
75	Door Coordinator	UL Listed, Monarch.
76	Precoated Galvolume Iron Profile Sheets.	Pennar, TATA Blue scope, NCL.
77	Multi Walled PolyCarbonate Roofing Sheets	Lexan, GE
78	Bitumen	Indian Oil, Hindustan Petroleum Corporation.
79	Aluminium Composite Panels (ACP)	Alstrong, Alucobond, Aluplex, Alubond.
80	Structural Glazing	Modi, Saint Gobain, Asahi, Glaverbel.
81.	Structural and Weather Sealants (Silicon)	Dow Corning, Wacker., GE, BASF
82	Adhesive Tape	Norton
83	Spider Patch Fittings for Structural Glazing	Dorma, Sevax, Kich, Ozone, Hafele.
84	G.I. Pipes -	TATA, Jindal, Zenith, Hissar.
85	G.I. Fittings	HB, R Brand, Unik, ICS.
86	Gun Metal Valves / Non Return Valves	Zoloto, Leader, Sant.
87	C.I. Sluice Valves (Double Flanged)	Zoloto, Leader, SANT, Kirloskar, IVC, Burn.
88	PTMT fittings/ fixtures	Prayag, Shakti, pearl.
89	C.P. Brass fittings/ fixtures	Jaquar , Marc, Plumber, ESS ESS, TOTO, Parko, Nova , Grohe.
90	C.P.V.C pipes & specials	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex, Flowguard.
91	UPVC Pipes & Fittings.	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex.
92	Poly Propylene Random Co polymer (PPR) Pipes & Specials	SFMC, Victus, Supreme, Prince.
93	Centrifugally Cast (spun) Pipes & Fittings (Sanitary Pipes)/ Centrifugally Cast iron hub less pipes	NECO , HEPCO, SKF, Bengal Iron Corporation (BIC) / NECO, kepsilan
94	Centrifugally Cast (spun) Pipes (LA) & Fittings (Water Supply Pipes) /	Electro steel, Kesoram, LANCO Industries, RIF, NECO./ NECO, kepsilan

95	Vitreous China Sanitary ware	Parryware, Neycer, Hindware, Cera, Jaquar, TOTO, Duravit.
96	Stainless Steel Sinks	Nirali, Kaff, Hindware, Johnson, Signature, Neelkanth, Cobra, Diamond.
97	Fire Clay Sinks	Sunfire, Parryware, Hindware.
98	Sensor Based Auto Flush Systems	A O S Systems, TOTO, Parryware, Hindware, Grohe, Kochler.
99	PVC Water Storage Tanks	Sintex, Uniplast, Durocon, Polycon, Supreme.
100	Float Valve (Ball Valve)	Prayag, Leader, Zoloto, IBP, Arco.
101	Water Meter	Zoloto, Leader, Dashmesh.
102		
	RCC Non Pressure (NP-2) Pipes -	Indo., Hindustan, Balaji Pipe Industries, Indian Hume Pipes Ltd.
103	Factory Made SFRC (RCC) Manhole Covers	Indo, Balaji Pipe Industries, Supreme.
104	CI Manhole Covers	SKF, HIF, Neco, Bengal Iron Corporation (BIC).
105	Coupler for reinforcement bars	LOKPAL Industries – Noida, Shree ISPAT Traders – Jaipur, Trimurthi Engg. & Fab Works – Nagpur, National cutting Tools Sai Couplings – Pune, SPROCS Rebar Couplings Kanva Trading – Chennai.

SCHEDULE OF QUANTITIES

Tender Inviting Authority: Registrar, MANUU

Name of Work: Construction of 'Silver Jubilee Gate-II' behind CIT building, MANUU Campus, Gachibowli, Hyderabad

Tender No: MANUU/Engg/2022-23/001

NOTE: The bidder should quote basic rates exclusive of GST and quote GST percentage separately; GST should be revised from time to time. However, the estimates rates are as per latest DSR/MR as adopted by CPWD, Hyderabad.

DSR. No.	Description of work	Qty	Unit	Basic Rate in Figures to be entered by the Bidder without GST	Add: GS T (%)	Total Amount without GST	Total Amount with GST	Total Amount with GSTin words
2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in chargex005f							
2.7.1	Ordinary rock	3.50	cum	475.88				
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:							
4.1.6	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	0.50	cum	7686.80				
5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete.							
5.33.1	All works upto plinth level							
5.33.1.2	Concrete of M25 grade with minimum cement content of 330 kg /cum	1.40	cum	9216.09				

5.33.2	All works above plinth level upto floor V level						
5.33.2.2	Concrete of M25 grade with minimum cement content of 330 kg/cum	1.00	cum	11616.36			
5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.						
5.22A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	350.00	kg	103.31			
5.9	Centering and shuttering including strutting, propping etc. and removal of form for						
5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	12.00	sqm	354.88			
5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	12.00	sqm	926.82			
10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.						
10.25.2	In gratings, frames, guard bar, ladder, railings, brackets,gates and similar works	1200.00	kg	163.99			
13.3	20 mm cement plaster of mix :						
13.3.2	1:6 (1 cement: 6 fine sand)	10.00	sqm	440.33			
13.8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	10.00	sqm	142.72			
3.46	Finishing walls with Acrylic Smooth exterior paint of required shade :				-		
13.46.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	10.00	sqm	192.28			
13.61.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:						

	Two or more coats on new work	36.00	sqm	151.48		
2.7(Repe ated)	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge.					
2.7.1(Repeated)	Ordinary rock	30.00	cum	475.88		
2.7.3	Hard rock (blasting prohibited)	80.00	cum	1364.79		
16.79	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achievethe desired density, complete as per specifications and directions of Engineer-in-Charge.	55.00	Cum	3230.93		
16.8	Construction of dry lean cement concrete sub base over a prepared sub-grade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer_x005fin- charge.	27.00	cum	4760.05		
4.6	Providing and fixing at or near ground level precast cement concrete in kerbs, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centering, shuttering complete.					
4.6.1A	1:1.5:3 (1 Cement: 1.5 coarse sand (zone-III) including manufactured sand derived from Recycled Concrete Aggregate (RCA) upto 25%: 3 graded stone aggregate 20 mm nominal size including Recycled Concrete Aggregate (RCA) upto 25%))	9.50	Cum	9107.24		

					T		1
13.61.1(Repeated	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:						
	Two or more coats on new work	83.00	sqm	151.48			
16.75	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator, vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in charge. (The panel shuttering work shall be paid for separately).	55.00	cum	9539.05			
16.1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and rerolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	560.00	sqm	208.01			
2.25(a)	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	260.00	cum	424.83			
2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	•					
2.8.1	All kinds of soil.	8.00	cum	330.57			
4.1(Repe ated-i)	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:						

				1			T
4.1.6(Rep eated-i)	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	1.20	cum	7686.80			
7.7	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with:						
7.7.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	13.00	cum	8505.12			
7.8	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level.						
7.8.2	Masonry work (second sort), in cement mortar 1:6 (1 cement: 6 coarse sand)	14.00	cum	10342.21			
15.9	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge:						
15.9.2	In cement mortar	14.00	Cum	2336.03			
13.33	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand):				÷		
13.33.2	Raised and cut pointing	62.00	Sqm	668.68			

16.53	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	11.00	metre	349.93		
5.33(Rep eated)	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete.	-				
5.33.2 (Repeate d)	All works above plinth level upto floor V level					
5.33.2.2(Repeated	Concrete of M25 grade with minimum cement content of 330 kg/cum	1.20	cum	11616.36		
peated)	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.					
5.22A.6(Repeated	Thermo-Mechanically Treated bars of grade Fe-500D or more.	100.00	kg	103.31		
2.1	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m: 2.10.1 All					

	kinds of soil						
2.10.1.3	Pipes, cables etc. exceeding 300 mm dia but not exceeding 600 mm	25.00	Cum	750.85		a	
2.13	Excavating trenches of required width for pipes, cables, etc, including excavation for sockets, depth upto 1.5 m, including getting out the excavated materials, returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layers by ramming, watering etc., stacking serviceable material for measurements and disposal of unserviceable material as directed, within a lead of 50 m: 2.13.1 Ordinary rock:						
2.13.1.3	Pipes, cables exceeding 300 mm dia but not exceeding 600 mm dia	25.00	Cum	1237.68			
4.1(Repe ated-ii)	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:						
4.1.6(Rep eated-ii)	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	6.00	cum	7686.80			
19.35	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C.pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc. complete				-		
19.35.2	600 mm dia RCC pipes.	50.00	metre	3516.61			
ITEM (Apprx Market	Supply of the following sizes of armoured XLPE insulated Aluminium conductor cable of 1.1 KV grade confirming to IS 7098 (Part-I) 1988 & part-II amended up to date with ISI mark complete as required						
	3.5 Core x 25 sqmm						
	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/ METAL pipe as required.	75.00	Meter	295.00			
7.5.1	3.5C x 25 Sqmm						
		75.00	Meter	37.00			
	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC						

political provided with a part of the provided with hinged/chained flush door of length not less than 30 mm at an elevation of 1.5 mm (28,70 mm) are plate shall be complete with 1.5 meters and a significant of 65.70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 30 mm at a relevation of 1.5 m (29,70 m) microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 30 mm at elevation of 1.5 m (29,70 m) mounting 40 pole connectors suitable for 4 core 10.16 Sq. mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 pole salul bena docks. Up Go 16 flowers well as per list of 60 shall be complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers well as plate shall be complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 40 flowers are complete as per drawing. The pole shall have a minimum of OAF of min at bottom and 70 mm at toot to the door of the flowers are complete as per drawing. The pole shall have a minimum of OAF of min at bottom and 70 mm at toot to the flowers are complete as per drawing. The pole shall have a minimum of OAF of John and toot to man 40 rom at a toot									_
9.1.20 3.5C X 25 sq. mm (28mm) 12.00 Each 313.00 Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to 18 14930, Part II complete with fifting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand custioning and protective overing etc., complete as required. 14.16.1 63 mm dia (0D-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the standard of		sheathed / XLPE aluminium conductor cable							
Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting and cutting excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protection of the cross of the protection of the		of 1.1 KV grade as required.							
Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting and cutting excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protection of the cross of the protection of the						l l			
Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting and cutting excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protective overing etc., complete as required. 14.16.163 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped and the protection of the cross of the protection of the	9.1.20	3.5C X 25 sq. mm (28mm)							
Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fifting and cutting. Jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped galvanized of meter height (Appr. oxer.) and the protection of the dipped galvanized of meter height (Appr. oxer.) and the protection of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS-8375, the HT steef for construction should be as per BSEN10025 grade S35510, minimum tickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS-2639/IS-2633/IS-4759 with average coating thickness of 6570 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Bra, Shorting links, end locks, UG able identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of Gi sheet of size not less than 200mmx20mmx12mm, 600mm long J' If foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as a principal and pole numbering etc as required. The pole shall be are a minimum of OAF of		2000000							
Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fifting and cutting. Jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped galvanized of meter height (Appr. oxer.) and the protection of the dipped galvanized of meter height (Appr. oxer.) and the protection of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS-8375, the HT steef for construction should be as per BSEN10025 grade S35510, minimum tickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS-2639/IS-2633/IS-4759 with average coating thickness of 6570 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Bra, Shorting links, end locks, UG able identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of Gi sheet of size not less than 200mmx20mmx12mm, 600mm long J' If foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as a principal and pole numbering etc as required. The pole shall be are a minimum of OAF of			12.00	Each	212.00	l.			
HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped ITEM (Apprx) cotagonal pole with 1.0 meter long Market in a proved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE ITR considering the wind speed as a per IS.873, the HT steel for construction should be as per BSEN10025 grade S35516, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS.262915/263315/4759 with average coating thickness of 6570 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelic sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG abel identification tags and pole numbering etc as required. The pole shall be mode of Gi sheet of size not less than 200mmx200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI weshers etc complete as per drawing. The pole shall be was a minimum of OAF of		0 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	12.00	Each	313.00	-			
accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing et.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 6 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped ITEM (Approx of Catagonia) pole with 1.0 meter long galvanized 5 meter height (Approx of Catagonia) pole with 1.0 meter long single arm Hot Dipped Galvanized apable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS-8375, the HT steef for construction should be as per BSEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external suralaceasa per IS-2629/IS-2633/IS-24759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be mode of Gi sheet of size not less than 200mmx200mmx12mm, 600mm long I' GI Foundation boils (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers et complete as a per drawing. The pole shall have and of GI sheet of size not less than 200mmx20mmx12mm and two GI washers et complete as a per unimium of OAF of									
conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including exeavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped galvanized 5 meter height (Apprx) cotagonal pole with 1.0 meter long Market in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade \$35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:263/IS:4759 with average coating thickness of 65:70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall he are a minimum of OAF of		HDPE pipe ISI marked along with all							
with fitting and cutting, iointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx oxpanal pole with 1.0 meter long single arm Hot Dipped Galvanized rate)-III capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR? considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65:70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (apprxox) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DN are shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be made of Gi sheet of size not less than 20 mm dia cach with three GI nuts and two GI swastes etc complete as per drawing. The pole shall be and of GI sheet of size not less than 20 mm dia cach with three GI nuts and two GI swastes etc complete as per drawing. The pole shall be are a minimum of OAF of									
with fitting and cutting, iointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx oxpanal pole with 1.0 meter long single arm Hot Dipped Galvanized rate)-III capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR? considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65:70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (apprxox) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DN are shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be made of Gi sheet of size not less than 20 mm dia cach with three GI nuts and two GI swastes etc complete as per drawing. The pole shall be and of GI sheet of size not less than 20 mm dia cach with three GI nuts and two GI swastes etc complete as per drawing. The pole shall be are a minimum of OAF of		conforming to IS 14930, Part II complete							
jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped galvanized 5 meter height (Approx Gagonal pole with 1.0 meter long Market single arm Hot Dipped Galvanized rate)-II (apple galvanized for holding the weight of the luminaire. The pole structural design shall be as per ILE TR? considering the wind speed as per IS.875, the HT steel for construction should be as per BSEN10025 grade \$35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS.2629/IS.263/IS.4759 with average coating thickness of 65770 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Bail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole ball be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers et complete as per drawing. The pole shall be are a minimum of OAF of									
ground level) including excavation and refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx oxpanisor) Market and the Dipped Galvanized single arm Hot Dipped Galvanized single arm Hot Dipped Galvanized for holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS-375, the HT steel for construction should be as per BSEN10025 grade S35510. minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS-2629/IS-2633/IS-4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 mps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.rnm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate with one of 19/16 Foundation botts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long "19 GI Foundation botts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall be made a minimum of OAF of						1			
refilling the trench but excluding sand cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped galvanized since the right (Apprx) octagonal pole with 1.0 meter long Market in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS.875, the HT steel for construction should be as per BEEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surrafacesas per IS.2629/IS.2633/I8.4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail,									
cushioning and protective overing etc., complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx Market galvanized 5 meter height (Apprx Market galvanized 6 meter height (Apprx of the luminaire. The pole structural design shall be as per ILE. TR? considering the wind speed as per ILE. TR? considering the wind speed as per IS.875, the HT steel for construction should be as per BSEN 10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS.26291S.2633/IS.4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4 for 6 Sq.									
complete as required. 14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) 90.00 Meter 247.00 Non DSR Supplying & Erection of Hot Dipped galvanized 5 meter height (Apprx) octagonal pole with 1.0 meter long Market single arm Hot Dipped Galvanized rate)-II gil bracket in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS.875, the HT steel for construction should be as per BSEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS.2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering et ca s required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'T GI Foundation botts (EM S Grade) of min. 20 mm dia each with three GI nuts and two GI washers et complete as per drawing, The pole shall have a minimum of OAF of									
14.16.1 63 mm dia (OD-63 mm & ID-51 mm nominal) Non DSR Supplying & Erection of Hot Dipped galvanized 5 meter height (Apprx octagonal pole with 1.0 meter long single arm Hot Dipped Galvanized of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS.875, the HT steel for construction should be as per BSEN10025 grade S35510. minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS.2629/IS.2633/IS.4759 with average coating thickness of 65/70 microros through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering et cas required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long T GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx Market rate)-II company									
Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx) octagonal pole with 1.0 meter long Market single arm Hot Dipped Galvanized rate)-II GI bracket in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade \$35516, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per 15:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'T GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of	14.16.1								
Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx Cagonal pole with 1.0 meter long Market single arm Hot Dipped Galvanized rate)-II Clapking to the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per ILS TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade \$35530, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long T' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		nominal)							
Non DSR Supplying & Erection of Hot Dipped ITEM galvanized 5 meter height (Apprx oragonal pole with 1.0 meter long Market single arm Hot Dipped Galvanized rate)-II Gi bracket in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade \$35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rai, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long T' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of	±	ž.	90.00	Meter	247.00				
(Apprx octagonal pole with 1.0 meter long Market single arm Hot Dipped Galvanized rate)-II GI bracket in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with abkelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering et as required. The pole shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of	Non DSR	Supplying & Frection of Hot Dipped							
Market gisle arm Hot Dipped Galvanized galvanized (Gi bracket in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS.875, the HT steel for construction should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS.2629/IS.2633/IS.4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of Gi sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' Gi Foundation bolts (EN & Grade) of min. 20 mm dia each with three Gi nuts and two Gi washers etc complete as per drawing. The pole shall have a minimum of OAF of									
Market single arm Hot Dipped Galvanized GI bracket in approved design Gapable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering et as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
rate)-II GI bracket in approved design capable of holding the weight of the luminaire. The pole structural design shall be as per IS-875, the HT steel for construction should be as per BENIOLOS grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafaceasa per IS-2629/IS-2633/IS-4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering et as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx20mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
capable of holding the weight of the luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S35510, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering et as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx20mmx20mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
luminaire. The pole structural design shall be as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx20mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of	rate)-11								
as per ILE TR7 considering the wind speed as per IS:875, the HT steel for construction should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering et cas required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
as per IS:875, the HT steel for construction should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafaceas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
as per IS:875, the HT steel for construction should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafaceas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		as per ILE TR7 considering the wind speed							
should be as per BSEN10025 grade S355Jo, minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long U GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		as per IS:875, the HT steel for construction							
minimum thickness 3 mm, hot dip galvanizing on both internal and external surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		should be as per BSEN10025 grade S355Jo.							
galvanizing on both internal and external surafacesas per Is:2629/Is:2633/Is:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		minimum thickness 3 mm hot din							
surafacesas per IS:2629/IS:2633/IS:4759 with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
with average coating thickness of 65/70 microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		surafacesas per 19.2620/19.2622/19.4750							
microns through a single dipping process. The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		with every 22 and the distance of (5/72)							
The pole shall also be provided with hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering et as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		with average coating thickness of 65//0							
hinged/chained flush door of length not less than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		inicrons through a single dipping process.							
than 300 mm at an elevation of 1.5m (approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		The pole shall also be provided with							
(approx) from the base plate with proper strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx20mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		hinged/chained flush door of length not less							
strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		than 300 mm at an elevation of 1.5m							
strengthing to the cutout of the door opening. Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx12mm, 600mm long 'I' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		(approx) from the base plate with proper						-	
Each pole shall be complete with a bakelite sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
sheet complete with DIN Rail, 2 amps, 10KA SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
SPN MCB, Screwless DIN mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		sheet complete with DIN Poil 2 amps 101/4							
mounting 4pole connectors suitable for 4 core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
core 10/16 Sq.mm cable terminations complete with DIN bar, shorting links, end locks,UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
complete with DIN bar, shorting links, end locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		mounting 4pole connectors suitable for 4							
locks, UG cable identification tags and pole numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		core 10/16 Sq.mm cable terminations							
numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		complete with DIN bar, shorting links, end							
numbering etc as required. The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		locks,UG cable identification tags and pole							
The pole shall be provided with 12 mm thick Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		numbering etc as required.							
Gussets welded the base plate and the base plate shall be made of GI sheet of size not less than 200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
plate shall be made of GI sheet of size not less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		Gussets welded the base plate and the base							
less than 200mmx200mmx12mm, 600mm long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		plate shall be made of GI sheet of size not							
long 'J' GI Foundation bolts (EN 8 Grade) of min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of		less than 200mmy200mmy12mm 600mm							
min. 20 mm dia each with three GI nuts and two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
two GI washers etc complete as per drawing. The pole shall have a minimum of OAF of									
The pole shall have a minimum of OAF of									
		wo of washers etc complete as per drawing.							
130mm at bottom and 70 mm at top. The 3.00 Each 38476.00		I ne pole shall have a minimum of OAF of							
		130mm at bottom and 70 mm at top. The	3.00	Each	38476.00		_		

ITEM (Apprx Market	die cast aluminium housing with IP 65/ 66 degree of protection, with built in surge protection device of 4 KV, color temperature 5700 - 6000 k, constant current driver suitable for operation on 230 volts single	2.00	Each	31037.00		
ITEM (Apprx Market rate)-III	Supply and laying of 3Core 1.5 sqmm size FR PVC insulated and FR PVC roundsheathed multicore copper conductor industrial cable of 1.1KV grade confirming to IS 694:1990 in PVC flexible pipe as required Supply of LED Flood light luminaire having	50.00	Meter	487.00		
Non Dan	Complex and the state of the st	1.00	Each	599.00		
2.10.2	Single pole and neutral	4.00	Each	256.00		
2.10.1	Single pole	g p.28	z.			
2 10 1	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.		Lacii	2200.00		
2.3.1	way, Double door	1.00	Each	2206.00		
2.3.1	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way, Double door					
pprx Market	recomendations and suitable 63mm dia DWC pipe for cable entry and Exit. (Design & drawing must be got approved from engineer-in-charge) Supply, installation, testing andcommissioning of LED street light fitting having die cast aluminium housing with buitin surge protecion device of 4KV, constant current driver complete with all accessories on the exisiting street light pole incuding connection with 3 x 1.5sqmm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required. (Luminaire rating not less than 70 watt)		Each	18119.00		
	pole shall have a section thickness of not less than 3 mm. The pole shall be fabricated in a single section. The pole and pole foundation should be got approved from Engineer- incharge. The item includes making RCC foundation (1:2:4 with 12mm reinforcement) for the pole as per OEM design and					

	phase, 50 Hz,AC supply complete with all accessories on wall/surface including						
	connections etc. as required. (Power rating not less than 200 W)						-
ITEM (Apprx Market	Supplying of LED post top made in die-cast aluminium bottom housing and spun aluminium top refector with decorative clear acrylic diffuser and IP65 protection. (Wattage not less than 45 W)		Each	25555.00			
1.17	Supply and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as required						
1.17.12	3 x 2.5 sq mm	-					
		90.00	meter	137.00			
1.21	Supplying nad fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.						
1.21.2	25mm						
		90.00	meter	145.00			
				26,00,094.0			
	Total Amount in Figures						
	Quoted rates in Words						
						Executi	Sd/- ve Engineer

Signature of Contractor

Check list for Technical eligibility of Tender

Sl No	Doc Ref	Description of the Document	Enclosed Yes/No	Remarks
1	NIT Para No 1	CPWD/MES/BSNL/Railway/State		
	Registration of	PWD(B&R) Autonomous bodies		
	Contractors	or undertakings.		
2	NIT Para No 1	Date of validity of enlistment		
	Eligible		-	
	Contractors/			
3	Details of	Not less than 40 % of estimated		
	works	cost (Three works of Building/		
	completed	Civil works)		
	during last 7	Not less than 50 % of estimated		
	years (Detailed	cost (Two works of Building/ Civil		
	statements to be	works)		
	enclosed)	Not less than 80 % of estimated		
*		cost (One work of Building/ Civil		
		works)		
		(Submit Details of works on which		
	10.00	contractor meets specified		
		eligibility criteria)		
4	As per the NIT	The tenderer shall have to furnish		
		an undertaking in prescribed		
		format. (form J)		
5	Annual	30% of the estimated cost.		
	turnover.			

Signature of the Contractor

Details of the Contractor

S.No.	Particulars	
1	Name of the Firm	
2	Name of the Contractor	
3	Contractor Details	
(a)	Mobile	
(b)	E-Mail id	
4	Name of the Bank	
5	Name of the Branch	
6	Account No. (prefix with zeros, if any as given on the cheque book/pass book) {please attach cancelled cheque}	
7	IFSC Code of the Branch	
8	MICR Code	
9	PAN No.	
10	GST No.(if applicable)	

Signature of Contractor