



HY/ADMN/ENGG/2020/F.43

Dated: 7/12/2021

Notice Inviting Quotation

NIQ No. MANUU/ES/F.43/2020-21 *06*
 2020-21

dated 7/12/2020

The I/c Engineering and Campus Development Section, MANUU Gachibowli, Hyderabad invites Sealed item rate quotations from reputed contractors/ service providers for the following work so as to reach this office up to 3.00 pm on or before 14/12/2021. The quotation will be opened on the same day at 3.30 PM. Blank quotation form can be downloaded from the website

Name of the work: *Repair of ROs in MANUU Campus, Hyderabad*

S.No.	Description	Qty	Unit	Rate		Amount
				In fig	In words	
1	500LPH Reverse Osmosis Plant at Boys Hostel-2 1.1 Repair and service of 1No. 1H.P, TOSHIO make, Single Phase pump which is the raw water feed pump 1.2 Repair and Service of 1No. 1H.P, CNP make, Single Phase pump which is the raw water feed pump 1.3 Repair and Service of 1No. 1100KW, CNP Make, Single Phase pump which is the High Pressure Feed pump 1.4 Repair and Service of 1No. Reverse Osmosis Plant Control Panel of ACCORD POWER make, LACRRR001 model so as to make it functioning in Auto Mode with all the control switches functional including all the in-line equipments/spares and 4" Composite Polymide R.O. Membrane Cleaning, including replacing miscellaneous petty items/accessories, consumables like U-PVC fittings, Synthetic Adhesive, SMB Push Type Fittings, Blue tubes, Teflon Tape, Salt, Dosing Chemical, 20" micron Filter etc., where ever required to make them functional.	LS				
2	500LPH Reverse Osmosis Plant at Boys Hostel-3 2.1 Repair and Service of 1No. 1H.P, CNP make, Single Phase pump which is the raw water feed pump 2.2 Repair, Replacement and Service of 1No. 1100KW, CNP Make, Single Phase pump which is the High Pressure Feed pump is having an issue and needs repair/servicing 2.3 Repair and Service of 1No. Reverse Osmosis Plant including all the in-line equipments/spares and 4" Composite	LS				



	Polymide R.O. Membrane Cleaning, including replacing miscellaneous petty items/accessories, consumables like U-PVC fittings, Synthetic Adhesive, SMB Push Type Fittings, Blue tubes, Teflon Tape, Salt, Dosing Chemical, 20" micron Filter etc., where ever required to make them functional.				
3	500LPH Reverse Osmosis Plant at School of Edu. & Training 3.1 Repair and Service of 1No. 0.62KW, Grundfos Make, Three Phase raw water feed 3.2 Repair and Service of 1No. Reverse Osmosis Plant including all the in-line equipments/spares and 4" Composite Polymide R.O. Membrane Cleaning, including replacing miscellaneous petty items/accessories, consumables like U-PVC fittings, Synthetic Adhesive, SMB Push Type Fittings, Blue tubes, Teflon Tape, Salt, Dosing Chemical, 20" micron Filter etc., where ever required to make them functional.	LS			
	Total :				

Term and conditions:

1. The work shall be executed as per manufacturers specification and terms and conditions enclosed with the Notice Inviting Quotation.
2. The time allowed for completion of work is 10 days from date of Issue of Work Order.
3. The rates should be quoted in figures and words and inclusive of GST and noting will be paid extra.
4. Necessary recoveries of IT and GST as applicable will be deducted from the gross amount of bill.
5. The payment will be made on after satisfactorily attending the maintenance work as required by Engg. Section.
6. The amount shall be inclusive of transportation and other incidental charges. No extra amount shall be paid by University.

CONTRACTOR

Address

Copy to

1. The Office of the Registrar
2. The Director CIT for uploading in the University website.
3. Notice Board

[Signature]
 7/12/21
 I/c Engg. & C.D Section

I/c Engineering Section

Maulana Azad National Urdu University

Gachibowli, Hyderabad-32

[Signature]