



NOTICE INVITING QUOTATION

Sealed item rate quotations are invited for “Electrical Works for establishing two (02) computer labs at MANUU CTE Darbhanga” to reach the office of the Principal, CTE MANUU CTE, Darbhanga Ilyas Ashrafnagar, Chandanpatti, Laheriasarai, Darbhanga - 846 002.

Notice Inviting Quotation No.	MANUU/ENGG/2024-25/F488/17 date 01-10-2024
Type of Tender/Form of Contract/ Bidding	Open/ Works Contract/
Name of Work	For Electrical Works for establishing two (02) computer labs at MANUU CTE Darbhanga
Estimated Amount	Rs 4,96,000/-
Earnest Money Deposit (EMD)	Rs 10,000/- (i.e. 2% of the estimated amount (DD/Bank Guarantee in favour of Finance Officer, MANUU payable at Hyderabad)
Performance Guarantee	5% of the Contract value (DD/Bank Guarantee in favour of Finance Officer, MANUU payable at Hyderabad)
Date of start of Bid Submission	03-10-2024 11:00 AM
Last date & Time for submission of Bids	24-10-2024 11:00 AM

Blank quotation form can be downloaded from the MANUU website.

fw
Alloy
at 10/1/24
I/c Engineering Section
I/c Engineering Section
MANUU
Maulana Azad National Urdu University
Gachibowli, Hyderabad-32

Zait
AE/EE

SCHEDULE OF QUANTITIES

Name of Work:		Electrical Works for establishing two (02) computer labs at MANUU CTE Darbhanga			
No:		MANUU/ENGG/2024-25/F488/			
DSR/MR No	Description of work	Qty	Unit	Rate	Amount
	UPS				
MR	Supply of line interactive UPS with AVR of following rating 2.0 KVA , MOSFET-PWM Technology, 60% or better Inverter Efficiency (%), Minimum 30 minutes battery backup time on Full Load, 230 Volts +/-15% Variation in AVR output in AC mode (AVR Voltage regulation) with inbuilt batteries complete as required.	11	Each		
	WIRING				
1.12	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	390	Meter		
1.14	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
1.14.10	4 X 10 sq. mm + 2 X 6 sq. mm earth wire	100	Meter		
MR	Supplying and fixing U-PVC cable management system of the following size polycarbonate, channel base, front cover, end covers including accessories, suitable on surface etc. as required				
MR	38 x 20 mm	120	Meter		
MR	50 x 20 mm	120	Meter		
	POWER OUTLETS				
MR/1.27	Supplying and fixing following size/modules PVC box along with modular base & cover plate for modular switches in recess etc. as required.				
MR/1.27.4	6 Module	101	Each		
1.24	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required				



DSR/MR No	Description of work	Qty	Unit	Rate	Amount
1.24.1	5/6 A switch	190	Each		
1.24.4	3 pin 5/6 A socket outlet	190	Each		
1.24.3	15/16 amps Switch	6	Each		
1.24.5	6 pin 15/16 A socket outlet	6	Each		
MR/1.57	Supplying & fixing suitable size PVC box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "C" curve including connections, painting etc. as required	6	Each		
	DB's, MCCB's & MCB's				
2.4	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
2.4.1	4 way (4 + 12), Double door	2	Each		
MR	Supplying and fixing following rating, 415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
MR	63 A FP MCB	2	Each		
2.10	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
2.10.1	Single pole (5-32 Amps) [18Nos C16 SPMCBs]	18	Each		
2.10.1	Single pole (5-32 Amps) [6Nos C25 SPMCBs]	6	Each		
	Total (in Rs.)				
	GST%				
	Total Amount (in Rs):				
	Quoted rates in Words				
				Sd/- I/c Engineering Section	

Details of the Contractor

S.No.	Particulars	To be filled by the Contractor
1	Name of the Firm	
2	Name of the Contractor	
3	Contractor Address	
(a)	Mobile	
(b)	E-Mail Id	
4	Name of the Bank	
5	Name of the Branch	
6	Account No.(prefix with zeros, if any as given on the cheque book/passbook)	
7	IFSC Code of the Branch	
8	MICR Code	
9	PAN No.	
10	GST No.	
11	State whether Terms & Conditions mentioned in the Quotation are accepted ? Yes/No	

I/we undertake and confirm that our firm/partnership firm has not been blacklisted by any state/Central Departments/PSUs/Autonomous bodies during its operations. Further, if such information comes to the notice of the University then I/we shall be liable for appropriate action as per the provisions laid down by the University or Govt. of India.

Signature of Contractor

Terms and Conditions

1. The work should be carried out strictly as per the specifications and as per the directions of the Principal, MANUU CTE Darbhanga.
2. Safety measures as specified in CPWD general conditions of contract should be adopted to protect the labour from every risk specifically while executing the work.
3. Before tendering, the contractor shall inspect site of work on all working days from 09:00 AM to 05:00 PM and shall fully acquaint himself about the conditions prevailing at site, availability of materials in market, availability of ready site and suitable locations for execution of the work involved in achieving the completion of work.
4. The contractor shall at his own expense and risk arrange the storage of materials at site of the work for carrying out of all jobs connected with the completion of the work. The contractor shall have to abide by the regulations of the authorities concerned and the directions of the Principal MANUU CTE Darbhanga. If during construction, it becomes necessary to remove or shift the equipment, material, etc, to facilitate execution, the contractor shall carry out the removal of shifting as directed by the Principal MANUU CTE Darbhanga and re-shift to its original position and no claim whatsoever, shall be entertained on this account.
5. It shall be deemed that the contractor has satisfied himself as to the nature and location of the work, transport facilities, availability of site, etc. the department will bear no responsibility for lack of such knowledge & the consequences thereof.
6. The Principal MANUU CTE Darbhanga shall have full powers for removal of any or all of the materials brought to site by contractor which are not in accordance with the contract specifications or do not conform, in character or quality. In case of default on the part of the contractor in removing rejected materials, the Principal MANUU CTE Darbhanga shall be at liberty to have them removed at the risk and cost of the contractor.
7. The work shall be carried out in such a manner so as not to interfere / or adversely / or disturb the functioning of the University and other works being executed by other agencies, if any.
8. Any damage done by the contractor to any existing work or work being executed by other agencies shall be made good by him at his own cost.
9. The contractor shall maintain in good condition all work executed till the completion of entire work entrusted to the contract under this contract.
10. No payment shall be made to the contractor for damage caused by rain, flood and other natural calamities whatsoever during the execution of works and any damage to the work on this account shall have to be made good by the contractor at his own cost.
11. The Contractor shall take instructions from the Principal MANUU CTE Darbhanga regarding collections and stacking of materials at site.
12. The Contractor shall be responsible to arrange at his own cost all necessary tools and tackles required for execution of the works including incidental original and maintenance works.
13. The operating cost of contractor's machinery at site i.e. Coolants/ lubricants/ Petrol/ Kerosene Oil/ Mobile Oil/ etc, if any shall be borne by the contractor himself.
14. The University shall not be responsible for any injury partial or permanent or death of any workers at site due to accident or malfunctioning of the equipment or by negligence of the Contractors staff on site.
15. If any damage caused for public conveniences/ services, the same shall have to be repaired instant, failing which necessary recovery shall be made from the bill.

16. If any Building, Road and Channels will be damaged by the Contractor the same will have to repair by the Contractor at his risk and cost, otherwise the complete cost will be recovered as intimated by the Principal MANUU CTE Darbhanga.
17. Price should be inclusive of all (transportation up to MANUU CTE Darbhanga Campus and all other incidental expenditure, if any).
18. Price of the items, GST% should be indicated separately.
19. No advance payment will be made.
20. Verbal quotation or incomplete quotation will be rejected.
21. Any variation in the specification(s) during repair/servicing will be rejected.
22. Time allowed is 21 days and starts from the date of issue of Work Order. In case of delay in completion of the contract, Liquidate damages (LD) at one percent of the contract value per week of delay subject to a maximum of ten percent of contract value shall be levied.
23. The work shall be carried out to the entire satisfaction of the the Principal, MANUU CTE Darbhanga..
24. Payment shall be made on submission of Invoice after satisfactory execution of the work and as per actual measurements
25. The rates quoted are net and nothing extra shall be paid on any account.
26. The tax as applicable shall be deducted from the gross amount of the bill.
27. The performance security will be forfeited and credited to the MANUU account in the event of a breach of contract by the contractor. However it shall be refunded to the contractor without interest after duly performs and complete all obligations.
28. The Security Deposit @ 2.5 percent on contract value shall be deducted and shall be refund on completion of Defect Liability Period of one year.

for
M. A. N. U. U.
09/10/19

I/c Engineering Section
I/c Engineering Section
Maulana Azad National Urdu University
Gachibowli, Hyderabad-32

-000-