



NOTICE INVITING QUOTATION

Sealed item rate quotations are invited for "Construction of RCC Slab for Over Head Tank at Type-V Staff Quarters in MANUU Campus, Gachibowli, Hyderabad" to reach the office of the Executive Engineer, Room No.22 Ground floor, Admin Building MANUU Gachibowli, Hyderabad.

Notice Inviting Quotation No. 13	MANUU/ENGG/2025-26/F425/ date α -10-2026
Type of Tender/Form of Contract/ Bidding	Open/ Works Contract/
Name of Work	For Construction of RCC Slab for Over Head Tank at Type-V Staff Quarters in MANUU Campus, Gachibowli, Hyderabad
Estimated Amount	Rs 57,449/-
Date of start of Bid Submission	01 -10-2026 @ 11:00 AM
Last date & Time for submission of Bids	08 -10-2026 @ 11:00 AM
Date of Opening of NIQ	08 -10-2026 @ 11: 30 AM

Blank quotation form can be downloaded from the MANUU website.

कार्यपालक अभियन्ता/Executive Engineer
MANUU
Executive Engineer
Maulana Azad National Urdu University, Hyd.

SCHEDULE OF QUANTITIES

Name of Work:		Construction of RCC Slab for Over Head Tank at Type-V Staff Quarters in MANUU Campus,Gachibowli, Hyderabad				
No:		MANUU/ENGG/2025-26/F543/				
S.No.	DSRNo	Description of Item	Qty	Unit	Rate	Amount
	15	DEMOLISHING				
1	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.24	Cum		
2		Reinforced Cement Concrete				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for :				
	5.9.3	Suspended floors, roofs, landings, balconies and access platform	15.50	Sqm		
3	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	134.30	Kg		
4	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete.				
	5.33.2	All works above plinth level upto floor V level				
	5.33.2.2	Concrete of M30 grade with minimum cement content of 350 kg /cum	1.84	Cum		
5	13	Finishing (Cement Plaster (in fine sand)				
		Cement Plaster With a Floating Coat Of Neat Cement				
	13.7	12 mm cement plaster finished with a floating coat of neat cement of mix :				
	13.7.1	1:3 (1 cement: 3 fine sand)	15.60	Sqm		
Total (excl GST)						
Add GST						
Total (Incl GST)						
Rupees in words.....						
.....						
						Sd/- Executive Engineer

Signature of Contractor with stamp

Details of the Contractor

S.No.	Particulars	To be filled by the Contractor
1	Name of the Firm	
2	Name of the Contractor	
3	Contractor Address	
(a)	Mobile	
(b)	E-Mail Id	
4	Name of the Bank	
5	Name of the Branch	
6	Account No.(prefix with zeros, if any as given on the cheque book/passbook)	
7	IFSC Code of the Branch	
8	MICR Code	
9	PAN No.	
10	GST No.	
11	State whether Terms & Conditions mentioned in the Quotation are accepted ? Yes/No	
12	Is EMD submitte/attached ? Yes/No	

I/we undertake and confirm that our firm/partnership firm has not been blacklisted by any state/Central Departments/PSUs/Autonomous bodies during its operations. Further, if such information comes to the notice of the University then I/we shall be liable for appropriate action as per the provisions laid down by the University or Govt. of India.

**** All the details sought in the above table shall be furnished mandatorily. Partially or incomplete form will not be considered. Further the intending bidders are required to submit a valid GST certificate mandatorily.**

Signature of Contractor

Details of the Contractor

S.No.	Particulars	To be filled by the Contractor
1	Name of the Firm	
2	Name of the Contractor	
3	Contractor Address	
(a)	Mobile	
(b)	E-Mail Id	
4	Name of the Bank	
5	Name of the Branch	
6	Account No.(prefix with zeros, if any as given on the cheque book/passbook)	
7	IFSC Code of the Branch	
8	MICR Code	
9	PAN No.	
10	GST No.	
11	State whether Terms & Conditions mentioned in the Quotation are accepted ? Yes/No	
12	Is EMD submitte/attached ? Yes/No	

I/we undertake and confirm that our firm/partnership firm has not been blacklisted by any state/Central Departments/PSUs/Autonomous bodies during its operations. Further, if such information comes to the notice of the University then I/we shall be liable for appropriate action as per the provisions laid down by the University or Govt. of India.

**** All the details sought in the above table shall be furnished mandatorily. Partially or incomplete form will not be considered. Further the intending bidders are required to submit a valid GST certificate mandatorily.**

Signature of Contractor

Terms and Conditions (नियम एवं शर्तें)

- 1) The work should be carried out strictly as per the specification and as per the directions Engineer-in-charge.
- 2) The intending bidder/agency/contractor may visit the campus to verify the requirements
- 3) The Defect Liability Period (DLP) for the work is 30 days from the date of completion of work. .
- 4) The performance Guarantee will be forfeited and credited to the MANUU account in the event of a breach of contract by the contractor.
- 5) Time allowed for completion of work is 30 days from the following date of issue of Work Order. In case of delay in completion of the contract, Liquidate damages (LD) at one percent of the contract value per week of delay subject to a maximum of ten percent of contract value shall be levied.
- 6) The participated bidders may be present during the opening of bids
- 7) Safety measures as specified in CPWD general conditions of contract should be adopted to protect the labour from every risk specifically while executing the work.
- 8) Before tendering, the contractor shall inspect site of work on all working days from 09:00 AM to 05:00 PM and shall fully acquaint himself about the conditions prevailing at site, availability of materials in market, availability of ready site and suitable locations for execution of the work involved in achieving the completion of work.
- 9) The contractor shall at his own expense and risk arrange the storage of materials at site of the work for carrying out of all jobs connected with the completion of the work. The contractor shall have to abide by the regulations of the authorities concerned and the directions of the Executive Engineer. If during construction, it becomes necessary to remove or shift the equipment, material, etc, to facilitate execution, the contractor shall carry out the removal of shifting as directed by the Executive Engineer and re-shift to its original position and no claim whatsoever, shall be entertained on this account.
- 10) It shall be deemed that the contractor has satisfied himself as to the nature and location of the work, transport facilities, availability of site, etc. the department will bear no responsibility for lack of such knowledge & the consequences thereof.
- 11) The Executive Engineer shall have full powers for removal of any or all of the materials brought to site by contractor which are not in accordance with the contract specifications or do not conform, in character or quality. In case of default on the part of the contractor in removing rejected materials, the I/c Engineering Section shall be at liberty to have them removed at the risk and cost of the contractor.
- 12) The work shall be carried out in such a manner so as not to interfere / or adversely / or disturb the functioning of the University and other works being executed by other agencies, if any.
- 13) Any damage done by the contractor to any existing work or work being executed by other agencies shall be made good by him at his own cost.

- 14) The contractor shall maintain in good condition all work executed till the completion of entire work entrusted to the contract under this contract.
- 15) No payment shall be made to the contractor for damage caused by rain, flood and other natural calamities whatsoever during the execution of works and any damage to the work on this account shall have to be made good by the contractor at his own cost.
- 16) The Contractor shall take instructions from the Executive Engineer regarding collections and stacking of materials at site.
- 17) The Contractor shall be responsible to arrange at his own cost all necessary tools and tackles required for execution of the works including incidental original and maintenance works.
- 18) The operating cost of contractor's machinery at site i.e. Coolants/ lubricants/ Petrol/ Kerosene Oil/ Mobile Oil/ etc, if any shall be borne by the contractor himself.
- 19) The University shall not be responsible for any injury partial or permanent or death of any workers at site due to accident or malfunctioning of the equipment or by negligence of the Contractors staff on site.
- 20) If any damage caused for public conveniences/ services, the same shall have to be repaired instant, failing which necessary recovery shall be made from the bill.
- 21) If any Building, Road and Channels damaged by the Contractor the same shall have to be repaired by the Contractor at his risk and cost, otherwise the complete cost will be recovered as intimated by the Executive Engineer.
- 22) The rate quoted by the contractor shall include all incidental expenses if any. No extra payment what so ever shall be paid to the contractor other than the quoted price.
- 23) Any variation in the specification(s) during repair/servicing/execution of work will be rejected. The work shall be carried out to the entire satisfaction of the Executive Engineer.
- 24) Payment shall be made on submission of Invoice after satisfactory execution of the work and as per actual measurements

कार्यपालक अभियन्ता /Executive Engineer

-000-

Executive Engineer
Maulana Azad National Urdu University, Hyd.