




NOTICE INVITING QUOTATION

Sealed item rate quotations are invited for “Construction of Aluminium Partition & Construction of platform in room at first floor of CPDUMT building in MANUU Campus Hyderabad” to reach the office of the Executive Engineer, Room No.22 Ground floor, Admin Building MANUU Gachibowli, Hyderabad.

Notice Inviting Quotation No. 14	MANUU/ENGG/2025-26/F543/ date 14-10-2026
Type of Tender/Form of Contract/ Bidding	Open/ Works Contract/
Name of Work	For Construction of Aluminium Partition & Construction of platform in room at first floor of CPDUMT building in MANUU Campus Hyderabad
Estimated Amount	Rs 81,959/-
Date of start of Bid Submission	14 -10-2026@ 11:00 AM
Last date & Time for submission of Bids	22-10-2026 @ 11:00 AM
Date of Opening of NIQ	23-10-2026 @ 11:00 AM

Blank quotation form can be downloaded from the MANUU website.


Executive Engineer
MANUU

Schedule of Quantities

Name of Work:		Construction of Aluminium Partition & Construction of platform in room at first floor of CPDUMT building in MANUU Campus Hyderabad				
No:		MANUU/ENGG/2025-26/F173/				
S.No.	DSR No	Description of Item	Qty	Unit	Rate	Amount
ALUMINIUM WORK						
1	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Zsections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
	21.1.1.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	50	kgs		
2	21.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge.				
	21.2.2	Pre-laminated particle board with decorative lamination on both sides	18	Sqm		
3	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.				
	21.8.1	Upto 5 mm depth and 5 mm width	25	mtr		
4	15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge				
	15.7.4	In cement mortar	2	cum		

S.No.	DSR No	Description of Item	Qty	Unit	Rate	Amount
Half Brick Masonry						
5	6.13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				
	6.13.1	Cement mortar 1:3 (1 cement :3 coarse sand)	6	Sqm		
Flooring						
6	16.87	Providing and laying gang saw cut 30 mm thick, mirror polished pre moulded and pre polished machine cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring in road side plazas and similar locations, laid over 20 mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etc. complete as per direction of Engineer-in-Charge				
	16.87.1	With granite stone of colour black, cherry/ruby red of area less than 0.50 sqm.	1.50	Sqm		
Finishing						
7	13	CEMENT PLASTER IN TWO COATS				
	13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	18	Sqm		
8	13.48	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	18	Sqm		
		Total (excl GST)				
		Add GST				
		Total (Incl GST)				
Rupees in words.....						

Signature of Contractor with stamp

Details of the Contractor

S.No.	Particulars	To be filled by the Contractor
1	Name of the Firm	
2	Name of the Contractor	
3	Contractor Address	
(a)	Mobile	
(b)	E-Mail Id	
4	Name of the Bank	
5	Name of the Branch	
6	Account No.(prefix with zeros, if any as given on the cheque book/passbook)	
7	IFSC Code of the Branch	
8	MICR Code	
9	PAN No.	
10	GST No.	
11	State whether Terms & Conditions mentioned in the Quotation are accepted ? Yes/No	
12	Is EMD submitte/attached ? Yes/No	

I/we undertake and confirm that our firm/partnership firm has not been blacklisted by any state/Central Departments/PSUs/Autonomous bodies during its operations. Further, if such information comes to the notice of the University then I/we shall be liable for appropriate action as per the provisions laid down by the University or Govt. of India.

**** All the details sought in the above table shall be furnished mandatorily. Partially or incomplete form will not be considered. Further the intending bidders are required to submit a valid GST certificate mandatorily.**

Signature of Contractor

Terms and Conditions

- 1) The work should be carried out strictly as per the specification and as per the directions Engineer-in-charge.
- 2) The intending bidder/agency/contractor may visit the campus to verify the requirements
- 3) The Defect Liability Period (DLP) for the work is 30 days from the date of completion of work. The PG shall be returned to the contractor without interest after completion of DLP.
- 4) Time allowed for completion of work is...14.....days from the following date of issue of Work Order. In case of delay in completion of the contract, Liquidate damages (LD) at one percent of the contract value per week of delay subject to a maximum of ten percent of contract value shall be levied.
- 5) The participated bidders may be present during the opening of bids
- 6) Safety measures as specified in CPWD general conditions of contract should be adopted to protect the labour from every risk specifically while executing the work.
- 7) Before tendering, the contractor shall inspect site of work on all working days from 09:00 AM to 05:00 PM and shall fully acquaint himself about the conditions prevailing at site, availability of materials in market, availability of ready site and suitable locations for execution of the work involved in achieving the completion of work.
- 8) The contractor shall at his own expense and risk arrange the storage of materials at site of the work for carrying out of all jobs connected with the completion of the work. The contractor shall have to abide by the regulations of the authorities concerned and the directions of the Executive Engineer. If during construction, it becomes necessary to remove or shift the equipment, material, etc, to facilitate execution, the contractor shall carry out the removal of shifting as directed by the Executive Engineer and re-shift to its original position and no claim whatsoever, shall be entertained on this account.
- 9) It shall be deemed that the contractor has satisfied himself as to the nature and location of the work, transport facilities, availability of site, etc. the department will bear no responsibility for lack of such knowledge & the consequences thereof.
- 10) The Executive Engineer shall have full powers for removal of any or all of the materials brought to site by contractor which are not in accordance with the contract specifications or do not conform, in character or quality. In case of default on the part of the contractor in removing rejected materials, the I/c Engineering Section shall be at liberty to have them removed at the risk and cost of the contractor.
- 11) The work shall be carried out in such a manner so as not to interfere / or adversely / or disturb the functioning of the University and other works being executed by other agencies, if any.
- 12) Any damage done by the contractor to any existing work or work being executed by other agencies shall be made good by him at his own cost.
- 13) The contractor shall maintain in good condition all work executed till the completion of entire work entrusted to the contract under this contract.

- 14) No payment shall be made to the contractor for damage caused by rain, flood and other natural calamities whatsoever during the execution of works and any damage to the work on this account shall have to be made good by the contractor at his own cost.
- 15) The Contractor shall take instructions from the Executive Engineer regarding collections and stacking of materials at site.
- 16) The Contractor shall be responsible to arrange at his own cost all necessary tools and tackles required for execution of the works including incidental original and maintenance works.
- 17) The operating cost of contractor's machinery at site i.e. Coolants/ lubricants/ Petrol/ Kerosene Oil/ Mobile Oil/ etc, if any shall be borne by the contractor himself.
- 18) The University shall not be responsible for any injury partial or permanent or death of any workers at site due to accident or malfunctioning of the equipment or by negligence of the Contractors staff on site.
- 19) If any damage caused for public conveniences/ services, the same shall have to be repaired instant, failing which necessary recovery shall be made from the bill.
- 20) If any Building, Road and Channels damaged by the Contractor the same shall have to be repaired by the Contractor at his risk and cost, otherwise the complete cost will be recovered as intimated by the Executive Engineer.
- 21) The rate quoted by the contractor shall include all incidental expenses if any. No extra payment whatsoever shall be paid to the contractor other than the quoted price.
- 22) Any variation in the specification(s) during repair/servicing will be rejected. The work shall be carried out to the entire satisfaction of the Executive Engineer.
- 23) Payment shall be made on submission of Invoice after satisfactory execution of the work and as per actual measurements


Executive Engineer

-000-